

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT ☐
(highlight changes)

APPLICATION FOR PERMIT TO DRILL				5. MINERAL LEASE NO. ML-23608	6. SURFACE: State
1A. TYPE OF WORK: DRILL <input checked="" type="checkbox"/> REENTER <input type="checkbox"/> DEEPEN <input type="checkbox"/>				7. IF INDIAN, ALLOTTEE OR TRIBE NAME:	
B. TYPE OF WELL: OIL <input type="checkbox"/> GAS <input checked="" type="checkbox"/> OTHER _____ SINGLE ZONE <input type="checkbox"/> MULTIPLE ZONE <input checked="" type="checkbox"/>				8. UNIT or CA AGREEMENT NAME: NATURAL BUTTES UNIT	
2. NAME OF OPERATOR: WESTPORT OIL & GAS COMPANY, L.P.				9. WELL NAME and NUMBER: NBU 1021-13G	
3. ADDRESS OF OPERATOR: 1368 S 1200 E CITY VERNAL STATE UT ZIP 84078			PHONE NUMBER: (435) 781-7060	10. FIELD AND POOL, OR WILDCAT: NATURAL BUTTES	
4. LOCATION OF WELL (FOOTAGES) AT SURFACE: 1444' FNL 2651' FEL 628223 X 39,951642 AT PROPOSED PRODUCING ZONE: 4423259 Y -109.498978				11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNE 13 10S 21E	
14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE: 19.35 MILES SOUTHEAST OF OURAY, UTAH				12. COUNTY: UINTAH	13. STATE: UTAH
15. DISTANCE TO NEAREST PROPERTY OR LEASE LINE (FEET) 1444'		16. NUMBER OF ACRES IN LEASE: 640		17. NUMBER OF ACRES ASSIGNED TO THIS WELL: 40	
18. DISTANCE TO NEAREST WELL (DRILLING, COMPLETED, OR APPLIED FOR) ON THIS LEASE (FEET) REFER TO TOPO C		19. PROPOSED DEPTH: 9,400		20. BOND DESCRIPTION: RLB0005238	
21. ELEVATIONS (SHOW WHETHER DF, RT, GR, ETC.): 5254.9' GL		22. APPROXIMATE DATE WORK WILL START:		23. ESTIMATED DURATION: TO BE DETERMINED	

PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	CASING SIZE, GRADE, AND WEIGHT PER FOOT			SETTING DEPTH	CEMENT TYPE, QUANTITY, YIELD, AND SLURRY WEIGHT			
	14"							
12 1/4"	9 5/8"	H-40	32.3#	2,000	PREM CMT	265 SX	1.18	15.6
7 7/8"	4 1/2"	I-80	11.6#	9,400	PREM LITE II	440 SX	3.38	11
					50/50 POZ G	1510 SX	1.31	14.3

ATTACHMENTS

VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES:

- | | |
|--|--|
| <input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER


<input checked="" type="checkbox"/> EVIDENCE OF DIVISION OF WATER RIGHTS APPROVAL FOR USE OF WATER | <input checked="" type="checkbox"/> COMPLETE DRILLING PLAN

<input type="checkbox"/> FORM 5, IF OPERATOR IS PERSON OR COMPANY OTHER THAN THE LEASE OWNER |
|--|--|

NAME (PLEASE PRINT) DEBRA DOMENICI TITLE ASSOC. ENVIRONMENTAL ANALYST
 SIGNATURE *Debra Domenici* DATE 2/3/2006

(This space for State use only)

API NUMBER ASSIGNED: 43-047-37723



T10S, R21E, S.L.B.&M.

R
21
E
R
22
E

Kerr-McGee Oil & Gas Onshore LP


Well location, NBU #1021-13G, located as shown in the SW 1/4 NE 1/4 of Section 13, T10S, R21E, S.L.B.&M. Uintah County, Utah.

BASIS OF ELEVATION

TWO WATER TRIANGULATION STATION LOCATED IN THE NW 1/4 OF SECTION 1, T10S, R21E, S.L.B.&M. TAKEN FROM THE BIG PACK MTN NE, QUADRANGLE, UTAH, UTAH COUNTY, 7.5 MINUTE QUAD. (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 5238 FEET.

BASIS OF BEARINGS

BASIS OF BEARINGS IS A G.P.S. OBSERVATION.



W 1/4 Cor. Sec. 18
1977 Brass Cap 0.7'
Above 0.5' High Pile
of Stones

18

SW Cor.
Sec. 18
1977 Brass
Cap 1.0'
High, Pile
of Stones,
Steel Post

THIS IS TO CERTIFY THAT THE ABOVE PROPERTY IS THE PROPERTY OF THE STATE OF UTAH, AS SHOWN IN THE FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

CERTIFICATE

REGISTERED LAND SURVEYOR
REGISTRATION NO. 161319
STATE OF UTAH

REVISED: 01-14-06

UINTAH ENGINEERING & LAND SURVEYING
85 SOUTH 200 EAST - VERNAL, UTAH 84078
(435) 789-1017


LEGEND:

└─┘ = 90° SYMBOL

● = PROPOSED WELL HEAD.

▲ = SECTION CORNERS LOCATED.

(NAD 83)
LATITUDE = 39°57'05.85" (39.951625)
LONGITUDE = 109°29'59.28" (109.499800)
(NAD 27)
LATITUDE = 39°57'05.97" (39.951658)
LONGITUDE = 109°29'56.81" (109.499114)



J NBU 1021-13G
SENE SEC 13-T10S-R21E
UINTAH COUNTY, UTAH
ML-23608

ONSHORE ORDER NO. 1

DRILLING PROGRAM

1. **Estimated Tops of Important Geologic Markers:**

<u>Formation</u>	<u>Depth</u>
Uinta	0- Surface
Green River	1400'
Wasatch	4500'
Mesaverde	7300'
TD	9400'

2. **Estimated Depths of Anticipated Water, Oil, Gas, or Mineral Formations:**

<u>Substance</u>	<u>Formation</u>	<u>Depth</u>
	Green River	1400'
Gas	Wasatch	4500'
Gas	Mesaverde	7300'
Water	N/A	
Other Minerals	N/A	

3. **Pressure Control Equipment** (Schematic Attached)

Please refer to the attached Drilling Program.

4. **Proposed Casing & Cementing Program:**

Please refer to the attached Drilling Program.

5. **Drilling Fluids Program:**

Please refer to the attached Drilling Program.

6. **Evaluation Program:**

Please refer to the attached Drilling Program.

7. **Abnormal Conditions:**

Maximum anticipated bottomhole pressure calculated at 9400' TD, approximately equals 5828 psi (calculated at 0.62 psi/foot).

Maximum anticipated surface pressure equals approximately 3760 psi (bottomhole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot).

8. **Anticipated Starting Dates:**

Drilling is planned to commence immediately upon approval of this application.

9. **Variances:**

Please refer to the attached Drilling Program.

10. **Other Information:**

Please refer to the attached Drilling Program.



Kerr-McGee Oil & Gas Onshore LP **DRILLING PROGRAM**

CASING PROGRAM

	SIZE	INTERVAL	WT.	GR.	CPLG.	DESIGN FACTORS		
						BURST	COLLAPSE	TENSION
CONDUCTOR	14"	0-40'				2270	1370	254000
SURFACE	9-5/8"	0 to 2000	32.30	H-40	STC	0.64*****	1.46	4.49
						7780	6350	201000
PRODUCTION	4-1/2"	0 to 9400	11.60	I-80	LTC	2.19	1.13	2.11

1) Max Anticipated Surf. Press. (MASP) (Surface Casing) = (Pore Pressure at next csg point - (0.22 psi/ft - partial evac gradient x TVD of next csg point))

2) MASP (Prod Casing) = Pore Pressure at TD - (.22 psi/ft - partial evac gradient x TD)

(Burst Assumptions: TD = 11.5 ppg)

.22 psi/ft = gradient for partially evac wellbore

(Collapse Assumption: Fully Evacuated Casing, Max MW)

(Tension Assumptions: Air Weight of Casing * Buoy. Fact. of water)

MASP 3553 psi

***** Burst SF is low but csg is much stronger than formation at 2000'. EMW @ 2000' for 2270# is 21.8 ppg or 1.13 psi/ft

CEMENT PROGRAM

		FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGHT	YIELD
SURFACE	LEAD	500	Premium cmt + 2% CaCl + .25 pps flocele	215	60%	15.60	1.18
Option 1	TOP OUT CMT (1)	200	20 gals sodium silicate + Premium cmt + 2% CaCl + .25 pps flocele	50		15.60	1.18
	TOP OUT CMT (2)	as required	Premium cmt + 2% CaCl	as req.		15.60	1.18
SURFACE	LEAD	1500	NOTE: If well will circulate water to surface, option 2 will be utilized Prem cmt + 16% Gel + 10 pps gilsonite + .25 pps Flocele + 3% salt BWOC	170	35%	11.00	3.82
Option 2	TAIL	500	Premium cmt + 2% CaCl + .25 pps flocele	180	35%	15.60	1.18
	TOP OUT CMT	as required	Premium cmt + 2% CaCl	as req.		15.60	1.18
PRODUCTION	LEAD	4,000'	Premium Lite II + 3% KCl + 0.25 pps celloflake + 5 pps gilsonite + 10% gel + 0.5% extender	440	60%	11.00	3.38
	TAIL	5,400'	50/50 Poz/G + 10% salt + 2% gel + .1% R-3	1510	60%	14.30	1.31

*Substitute caliper hole volume plus 0% excess for LEAD if accurate caliper is obtained

*Substitute caliper hole volume plus 15% excess for TAIL if accurate caliper is obtained

FLOAT EQUIPMENT & CENTRALIZERS

SURFACE	Guide shoe, 1 jt, insert float. Centralize first 3 joints with bow spring centralizers. Thread lock guide shoe.
PRODUCTION	Float shoe, 1 jt, float collar. Centralize first 3 joints & every third joint to top of tail cement with bow spring centralizers.

ADDITIONAL INFORMATION

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.

BOPE: 11" 5M with one annular and 2 rams. Test to 5,000 psi (annular to 2,500 psi) prior to drilling out. Record on chart recorder &

tour sheet. Function test rams on each trip. Maintain safety valve & inside BOP on rig floor at all times. Kelly to be equipped with upper

& lower kelly valves.

Drop Totco surveys every 2000'. Maximum allowable hole angle is 5 degrees.

Most rigs have PVT Systems for mud monitoring. If no PVT is available, visual monitoring will be utilized.

DRILLING ENGINEER:

Brad Laney

DATE:

DRILLING SUPERINTENDENT:

Randy Bayne

DATE:

NBU 1021-13G
SWNE SEC 13-T10S-R21E
Uintah County, UT
ML-23608

ONSHORE ORDER NO. 1

MULTI-POINT SURFACE USE & OPERATIONS PLAN

1. Existing Roads:

Refer to Topo Map A for directions to the location.

Refer to Topo Maps A and B for location of access roads within a 2-mile radius.

Refer to Topo Maps A and B for location of access roads within a 2 mile radius.

All existing roads will be maintained and kept in good repair during all drilling and completion operations associated with this well.

2. Planned Access Roads:

Approximately 0.25 miles of new access road is proposed. Refer to Topo Map B for the location of the proposed access road.

The upgraded and new portions of the access road will be crowned and ditched with a running surface of 18 feet and a maximum disturbed width of 30 feet. Appropriate water control will be installed to control erosion.

Existence of pipelines; maximum grade; turnouts; major cut and fills, culverts, or bridges; gates, cattle guards, fence cuts, or modifications to existing facilities were determined at the on-site.

The access road was centerline flagged during time of staking.

Surfacing material may be necessary, depending upon weather conditions.

Surface disturbance and vehicular traffic will be limited to the approved location and approved access route. Any additional area needed will be approved in advance.

3. Location of Existing Wells Within a 1-Mile Radius

Please refer to Topo Map C.

4. Location of Existing & Proposed Facilities

The following guidelines will apply if the well is productive.

All production facilities will be located on the disturbed portion of the well pad and at a minimum of 25 feet from the toe of the back slope or the top of the fill slope.

A dike will be constructed completely around those production facilities which contain

fluids (i.e., production tanks, produced water tanks, and/or heater/treater). These dikes will be constructed of compacted subsoil, be impervious, hold 100% of the capacity of the largest tank, and be independent of the back cut.

All permanent (on-site six months or longer) above the ground structures constructed or installed, including pumping units, will be painted a flat, non-reflective, earthtone color to match one of the standard environmental colors, as determined by the five state Rocky Mountain Inter-Agency Committee.

All facilities will be painted within six months of installation. Facilities required to comply with the Occupational Safety and Health Act (OSHA) will be excluded. The required color is Carlsbad Canyon, standard color number 2.5Y 6/2.

Any necessary pits will be properly fenced to protect livestock and prevent wildlife entry.

Approximately 1430' of pipeline is proposed. Refer to Topo D for the proposed pipeline.

5. Location and Type of Water Supply:

Water for drilling purposes will be obtained from Dalbo Inc.'s underground well located in Ouray, Utah, Sec. 32, T4S, R3E, Water User Claim #43-8496, Application #53617.

Water will be hauled to location over the roads marked on Maps A and B.

No water well is to be drilled on this lease.

6. Source of Construction Materials

Surface and subsoil materials in the immediate area will be utilized.

Any gravel will be obtained from a commercial source.

7. Methods of Handling Waste Materials

Drill cuttings will be contained and buried in the reserve pit.

Drilling fluids, including salts and chemicals, will be contained in the reserve pit. Upon termination of drilling and completion operations, the liquid contents of the reserve pit will be removed and disposed of at an approved waste disposal facility within 120 days after drilling is terminated.

The reserve pit will be constructed on the location and will not be located within natural drainage, where a flood hazard exists or surface runoff will destroy or damage the pit walls. The reserve pit will be constructed so that it will not leak, break, or allow discharge of liquids.

A plastic reinforced liner and felt will be used, it will be a minimum of 20 mil thick, with sufficient bedding used to cover any rocks. The liner will overlap the pit walls and be covered with dirt and/or rocks to hold it in place. No trash or scrap that could puncture the liner will be disposed of in the pit.

Any spills of oil, gas, salt water, or other noxious fluids will be immediately cleaned up and removed to an approved disposal site.

A chemical porta-toilet will be furnished with the drilling rig.

Garbage, trash, and other waste materials will be collected in a portable, self-contained, fully enclosed trash cage during operations. No trash will be burned on location.

All debris and other waste material not contained in the trash cage will be cleaned up and removed from the location immediately after removal of the drilling rig.

Any open pits will be fenced during the operations. The fencing will be maintained until such time as the pits are backfilled.

No chemicals subject to reporting under SARA Title III (hazardous materials) in an amount greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling of this well.

Any produced water from the proposed well will be contained in a water tank and will then be hauled by truck to one of the pre-approved disposal sites: RNI, Sec. 5, T9S, R22E, NBU #159, Sec. 35, T9S, R21E, Ace Oilfield, Sec. 2, T6S, R20E, MC&MC, Sec. 12, T6S, R19E.

8. Ancillary Facilities

None are anticipated.

9. Well Site Layout: (See Location Layout Diagram)

The attached Location Layout Diagram describes drill pad cross-sections, cuts and fills, and locations of the mud tanks, reserve pit, flare pit, pipe racks, trailer parking, spoil dirt stockpile(s), and surface material stockpile(s).

Please see the attached diagram to describe rig orientation, parking areas, and access roads.

The reserve pit will be lined, and when the reserve pit is closed, the pit liner will be buried below plow depth.

All pits will be fenced according to the following minimum standards:

39 inch net wire will be used with at least one strand of barbed wire on top of the net wire. Barbed wire is not necessary if pipe or some type of reinforcement rod is attached to the top of the entire fence.

The net wire shall be no more than two inches above the ground. The barbed wire shall be three inches over the net wire. Total height of the fence shall be at least 42 inches.

Corner posts shall be cemented and/or braced in such a manner to keep the fence tight at all times.

Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distance between any 2 fence posts shall be no greater than 16 feet.

All wire shall be stretched, by using a stretching device, before it is attached to corner posts.

The reserve pit fencing will be on three sides during drilling operations, and on the fourth side when the rig moves off location. Pits will be fenced and maintained until cleanup.

Location size may change prior to the drilling of the well due to current rig availability. If the proposed location is not large enough to accommodate the drilling rig the location will be re-surveyed and a Form 9 shall be submitted.

10. Plans for Reclamation of the Surface:

Producing Location:

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, materials, trash, and debris not required for production.

Immediately upon well completion, any hydrocarbons in the pit shall be removed in accordance with 43 CFR 3162.7-1.

A plastic, nylon reinforced liner will be used, it shall be torn and perforated before backfilling of the reserve pit.

Before any dirt work associated with location restoration takes place, the reserve pit shall be as dry as possible. All debris in it will be removed. Other waste and spoil materials will be disposed of immediately upon completion of operations.

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximate natural contours. The reserve pit will be reclaimed within 90 days from the date of well completion, weather permitting.

To prevent surface water (s) from standing (ponding) on the reclaimed reserve pit area, final reclamation of the reserve pit will consist of "mounding" the surface three feet above surrounding ground surface to allow the reclaimed pit area to drain effectively.

Upon completion of backfilling, leveling, and recontouring, the stockpiled topsoil will be spread evenly over the reclaimed area(s).

Dry Hole/Abandoned Location:

Abandoned well sites, roads, and other disturbed areas will be restored as near as practical to their original condition. Where applicable, these conditions include the re-establishment of irrigation systems, the re-establishment of appropriate soil conditions, and re-establishment of vegetation as specified.

All disturbed surfaces will be recontoured to the approximate natural contours, with reclamation of the well pad and access road to be performed as soon as practical after final abandonment. Reseeding operations will be performed after completion of other reclamation operations.

11. **Surface Ownership:**

SITLA
675 East 500 South, Suite 500
Salt Lake City, UT 84102

12. **Other Information:**

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, the approved Plan of Operations, and any applicable Notice of Lessees. The Operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished to the field representative to ensure compliance.

The Operator will control noxious weeds along Rights-Of-Way for roads, pipelines, well sites, or other applicable facilities.

A Class III archaeological survey has been completed and is attached.

This location is not within 460' from the boundary of the Natural Buttes Unit, nor is it Within 460' of any non-committed tract lying within the boundaries of the Unit.

13. **Lessee's or Operators's Representative & Certification:**

Debra Domenici
Associate Environmental Analyst
Kerr-McGee Oil & Gas Onshore LP
1368 South 1200 East.
Vernal, UT 84078
(435) 781-7060

Randy Bayne
Drilling Manager
Kerr-McGee Oil & Gas Onshore LP
1368 South 1200 East
Vernal, UT 84078
(435)781-7018


Certification: All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved Plan of Operations, and any applicable Notice to Lessees.

The Operator will be fully responsible for the actions of its subcontractors. A complete copy of the approved "Application for Permit to Drill" will be furnished to the field representative(s) to ensure compliance and shall be on location during all construction and drilling operations.

Kerr-McGee Oil & Gas Onshore LP is considered to be the operator of the subject well. Kerr-McGee Oil & Gas Onshore LP agrees to be responsible under terms and conditions of the lease for the operations conducted upon leased lands.

Bond coverage pursuant to 43 CFR 3104 for lease activities is being provided by State Surety Bond #RLB0005236.

I hereby certify that I, or persons under my supervision, have inspected the proposed drill site and access route, that I am familiar with the conditions that currently exist; that the statements made in this plan are, to the best of my knowledge, true and correct; and the work associated with the operations proposed herein will be performed by the Operator, its contractors, and subcontractors in conformity with this plan and the terms and conditions under which it is approved.


Debra Domenici

2/3/2006

Date

Kerr-McGee Oil & Gas Onshore LP
NBU #1021-13G
SECTION 13, T10S, R21E, S.L.B.&M.

PROCEED IN A WESTERLY DIRECTION FROM VERNAL, UTAH ALONG U.S. HIGHWAY 40 APPROXIMATELY 14.0 MILES TO THE JUNCTION OF STATE HIGHWAY 88; EXIT LEFT AND PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 17.0 MILES TO OURAY, UTAH; PROCEED IN A SOUTHERLY, THEN SOUTHEASTERLY DIRECTION APPROXIMATELY 11.2 MILES ON THE SEEP RIDGE ROAD TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE EAST; TURN LEFT AND PROCEED IN AN EASTERLY, THEN SOUTHEASTERLY DIRECTION APPROXIMATELY 6.2 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE NORTHEAST; TURN LEFT AND PROCEED IN A NORTHEASTERLY DIRECTION APPROXIMATELY 1.6 MILES TO THE BEGINNING OF THE PROPOSED ACCESS FOR THE #1021-13C TO THE NORTHEAST; FOLLOW ROAD FLAGS IN A NORTHEASTERLY DIRECTION APPROXIMATELY 0.1 MILES TO THE BEGINNING OF THE PROPOSED ACCESS TO THE EAST; FOLLOW ROAD FLAGS IN AN EASTERLY DIRECTION APPROXIMATELY 0.25 MILES TO THE PROPOSED LOCATION.

TOTAL DISTANCE FROM VERNAL, UTAH TO THE PROPOSED WELL LOCATION IS APPROXIMATELY 50.35 MILES.

Kerr-McGee Oil & Gas Onshore LP

NBU #1021-13G

LOCATED IN UINTAH COUNTY, UTAH

SECTION 13, T10S, R21E, S.L.B.&M.



PHOTO: VIEW FROM CORNER #5 TO LOCATION STAKE

CAMERA ANGLE: SOUTHERLY



PHOTO: VIEW FROM BEGINNING OF PROPOSED ACCESS

CAMERA ANGLE: EASTERLY



- Since 1964 -

U E L S Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
435-789-1017 uels@uelsinc.com

LOCATION PHOTOS

12 01 05
MONTH DAY YEAR

PHOTO

TAKEN BY: P.J.

DRAWN BY: C.P.

REVISED: 01-14-06

Kerr-McGee Oil & Gas Onshore LP

NBU #1021-13G

PIPELINE ALIGNMENT

LOCATED IN UTAH COUNTY, UTAH

SECTION 13, T10S, R21E, S.L.B.&M.



PHOTO: VIEW FROM TIE-IN POINT

CAMERA ANGLE: WESTERLY



PHOTO: VIEW OF PIPELINE ALIGNMENT

CAMERA ANGLE: EASTERLY



- Since 1964 -

UELS Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
435-789-1017 uels@uelsinc.com

PIPELINE PHOTOS

12 01 05
MONTH DAY YEAR



PHOTO


TAKEN BY: P.J.

DRAWN BY: C.P.

REVISED: 01-14-06

5M BOP STACK and CHOKE MANIFOLD SYSTEM





LEGEND:

⊙ PROPOSED LOCATION

Kerr-McGee Oil & Gas Onshore LP

NBU #1021-13G

SECTION 13, T10S, R21E, S.L.B.&M.

1444' FNL 2651' FEL



Utah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813




TOPOGRAPHIC
MAP

12 01 05
MONTH DAY YEAR

SCALE: 1:100,000 **DRAWN BY: C.P.** **REVISED: 01-14-06**





LEGEND:

EXISTING ROAD
 PROPOSED ACCESS ROAD

Kerr-McGee Oil & Gas Onshore LP

NBU #1021-13G
 SECTION 13, T10S, R21E, S.L.B.&M.
 1444' FNL 2651' FEL




Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813


TOPOGRAPHIC
 MAP

12 01 05
 MONTH DAY YEAR

SCALE: 1" = 2000' DRAWN BY: C.P. REVISED: 01-14-06







APPROXIMATE TOTAL PIPELINE DISTANCE = 1,430' +/-

LEGEND:

- PROPOSED ACCESS ROAD
- EXISTING PIPELINE
- - - - PROPOSED PIPELINE
- - - - PROPOSED PIPELINE (SERVICING OTHER WELLS)



Kerr-McGee Oil & Gas Onshore LP

NBU #1021-13G
SECTION 13, T10S, R21E, S.L.B.&M.
1444' FNL 2651' FEL



Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813

TOPOGRAPHIC
MAP

12 01 05
 MONTH DAY YEAR

SCALE: 1" = 1000' DRAWN BY: C.P. REVISED: 01-14-06



Kerr-McGee Oil & Gas Onshore LP


FIGURE #1

LOCATION LAYOUT FOR

NBU #1021-13G
SECTION 13, T10S, R21E, S.L.B.&M.
1444' FNL 2651' FEL

Proposed Access Road
for the #1021-13A


CONSTRUCT
DIVERSION
DITCH



SCALE: 1" = 50'
DATE: 12-11-05
Drawn By: P.M.
Revised: 01-14-06

NOTE:

Flare Pit is to be located
a min. of 100' from the
Well Head.



NOTES:

Elev. Ungraded Ground At Loc. Stake = 5256.0'
FINISHED GRADE ELEV. AT LOC. STAKE = 5254.9'

UINTAH ENGINEERING & LAND SURVEYING
85 So. 200 East * Vernal, Utah 84078 * (435) 789-1017

Kerr-McGee Oil & Gas Onshore LP

FIGURE #2

TYPICAL CROSS SECTIONS FOR

NBU #1021-13G

SECTION 13, T10S, R21E, S.L.B.&M.


1444' FNL 2651' FEL

1" = 20'
X-Section
Scale
1" = 50'

DATE: 12-11-05

Drawn By: P.M.

Revised: 01-14-06



NOTE:

Topsoil should not be Stripped Below Finished Grade on Substructure Area.

* NOTE:

FILL QUANTITY INCLUDES 5% FOR COMPACTION

APPROXIMATE YARDAGES

CUT		
(6") Topsoil Stripping	=	1,830 Cu. Yds.
Remaining Location	=	8,060 Cu. Yds.
TOTAL CUT	=	9,890 CU.YDS.
FILL	=	3,400 CU.YDS.

EXCESS MATERIAL	=	6,490 Cu. Yds.
Topsoil & Pit Backfill (1/2 Pit Vol.)	=	3,970 Cu. Yds.
EXCESS UNBALANCE (After Rehabilitation)	=	2,520 Cu. Yds.

UINTAH ENGINEERING & LAND SURVEYING
85 So. 200 East * Vernal, Utah 84078 * (435) 789-1017

WORKSHEET
APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 02/08/2006

API NO. ASSIGNED: 43-047-37723

WELL NAME: NBU 1021-13G

OPERATOR: WESTPORT OIL & GAS CO (N2115)

PHONE NUMBER: 435-781-7060

CONTACT: DEBRA DOMENICI

PROPOSED LOCATION:

SWNE 13 100S 210E

SURFACE: 1444 FNL 2651 FEL

BOTTOM: 1444 FNL 2651 FEL

COUNTY: Uintah

LATITUDE: 39.95164 LONGITUDE: -109.4990

UTM SURF EASTINGS: 628223 NORTHINGS: 4423259

FIELD NAME: NATURAL BUTTES (630)

INSPECT LOCATN BY: / /

Tech Review	Initials	Date
Engineering	DGD	3/14/06
Geology		
Surface		

LEASE TYPE: 3 - State

LEASE NUMBER: ML-23608

PROPOSED FORMATION: WSMVD

SURFACE OWNER: 3 - State

COALBED METHANE WELL? NO

RECEIVED AND/OR REVIEWED:

- ☒ Plat
- ☒ Bond: Fed[] Ind[] Sta[] Fee[]
(No. RLB0005236)
- ☐ Potash (Y/N)
- ☒ Oil Shale 190-5 (B) or 190-3 or 190-13
- ☒ Water Permit
(No. 43-8496)
- ☐ RDCC Review (Y/N)
(Date:)
- ☐ Fee Surf Agreement (Y/N)
- ☐ Intent to Commingle (Y/N)

LOCATION AND SITING:

- ___ R649-2-3.
- Unit: NATURAL BUTTES
- ___ R649-3-2. General
Siting: 460' From Qtr/Qtr & 920' Between Wells
- ___ R649-3-3. Exception
- ☒ Drilling Unit
Board Cause No: 173-14
Eff Date: 12-2-1999
Siting: 460' fr Wbdry of unconsolidated
- ___ R649-3-11. Directional Drill

COMMENTS:

Need Private (02-23-06)

STIPULATIONS:

- 1- OIL SHALE*
- 2- STATEMENT OF BASIS*
- 3- Surface Csg Cont Stip*

**DIVISION OF OIL, GAS AND MINING
APPLICATION FOR PERMIT TO DRILL
STATEMENT OF BASIS**

OPERATOR: Westport Oil & Gas Company, L.P.
WELL NAME & NUMBER: NBU 1021-13G
API NUMBER: 43-047-37723
LOCATION: 1/4, 1/4 SW/NE Sec: 13 TWP: 10S RNG: 21E; 1444 FNL 2651' FEL

Geology/Ground Water:

Westport proposes to set 2,000' of surface casing at this location. The depth to the base of the moderately saline water at this location is estimated to be at a depth of 5,300'. A search of Division of Water Rights records shows one water well within a 10,000 foot radius of the center of Section 13. This well is over a mile from the proposed site. The well is owned by Target Trucking and is an oilfield water supply well. No depth for the well is listed. The surface formation at this site is the Uinta Formation. The Uinta Formation is made up of interbedded shales and sandstones. The sandstones are mostly lenticular and discontinuous and should not be a significant source of useable ground water. The production casing cement should be brought above the base of the moderately saline groundwater to isolate it from fresher waters uphole.

Reviewer: Brad Hill **Date:** 03/06/06

Surface:

The pre-drill investigation of the surface was performed on February 23, 2006. Ed Bonner and Jim Davis of SITLA and Ben Williams of UDWR were invited to attend the presite on Feb.14, 2006. Mr. Davis and Mr. Williams attended.

The site is State Surface and State Mineral. The proposed location poses no obvious problems for drilling and appears to be the best location for drilling a well in the immediate area.

A paleontological survey was completed by IPC on 9/26/05 and furnished for the file. The access road leading to the site will be moved 5 meters to avoid a formation, which may contain paleontological resources.

Mr. Williams of the UDWR stated that the area is classified as critical yearlong antelope range, however he did not recommend any stipulations, as water is the limiting factor affecting the population not forage. The UDWR database shows a red tailed hawk nest in ledges south and east of the location. It is not known if it has had recently activity. He suggested a restriction period from 4/1-7/15 for road and pad construction, drilling and workover rigs. If Westport desires any of these activities during that period, he will check the nest to see if is or has had recent activity. No other wildlife are expected to be affected. He gave Mr. Davis and Mr. Estes copies of his write-up and a DWR recommended seed mix to use on the reserve pit and when closing the location.

Reviewer: Floyd Bartlett **Date:** 03/03/2006

Conditions of Approval/Application for Permit to Drill:

1. A synthetic liner with a minimum thickness of 16 mils with a felt sub-liner shall be properly installed and maintained in the reserve pit.

ON-SITE PREDRILL EVALUATION
Division of Oil, Gas and Mining

OPERATOR: Westport Oil & Gas Company, L.P.
WELL NAME & NUMBER: NBU 1021-13G
API NUMBER: 43-047-37723
LEASE: ML-23608 **FIELD/UNIT:** Natural Buttes
LOCATION: 1/4, 1/4 SW/NE **Sec:** 13 **TWP:** 10S **RNG:** 21E ; 1444 FNL 2651' FEL
LEGAL WELL SITING: 460' from unit boundary and uncommitted tracts.
GPS COORD (UTM): 4423259 Y 0628223 X **SURFACE OWNER:** State of Utah
(SITLA)

PARTICIPANTS

Floyd Bartlett and David Hackford (DOGM), Carol Estes, Debora Domenici, Clay Einerson (Westport), David Kay and Luke Kay (Uintah Engineering & Land Survey), Jim Davis (SITLA), Ben Williams (Utah Division of Wildlife Resources).

REGIONAL/SETTING TOPOGRAPHY

General area is the Sand Wash Drainage of Uintah, County. Sand Wash is approximately 36 air miles south of Vernal, Utah and approximately 19 miles southeast of Ouray, Utah. Access is by State of Utah Highway, Uintah County and oilfield development roads.

Topography is characterized by broad open flats dissected by numerous sub-drainages, which often become steep with ridges and draws with exposed sandstone layers. No perennial streams occur in drainage. Individual draws or washes are ephemeral with spring runoff or flows from sometimes-intense summer rainstorms. White River is to the northeast about 4 miles. No springs exist in the area. An occasional constructed pond occurs furnishing water for antelope or livestock.

This site is approximately ½ mile west of Sand Wash on a small saddle on a east-west running ridge. The ridge breaks sharply to the north and south. One short drainage originates within the location and will be covered with fill. No stabilization problems are likely to occur. Approximately 0.25 miles of new road will be constructed from the road planned for the NBU 1021-13C.

SURFACE USE PLAN

CURRENT SURFACE USE: Sheep grazing, limited hunting and recreation.

PROPOSED SURFACE DISTURBANCE: Location of 350' x 193' and a reserve pit of 100' x 150' x 10 feet deep and an additional 15' wide bench. Approximately 0.25 miles of new road will be required. All material for the location and road will be obtained onsite.

LOCATION OF EXISTING WELLS WITHIN A 1 MILE RADIUS: See attached map

from GIS data base.

LOCATION OF PRODUCTION FACILITIES AND PIPELINES: All production facilities will be on location and added after drilling well. Pipeline will follow access road.

SOURCE OF CONSTRUCTION MATERIAL: All construction material will be obtained from the site.

ANCILLARY FACILITIES: None will be required.

WILL DRILLING AT THIS LOCATION GENERATE PUBLIC INTEREST CONCERNS? (EXPLAIN). Unlikely, as the general use in the area is oil-field related with numerous other wells in the surrounding area.

WASTE MANAGEMENT PLAN:

Drilled cuttings will be settled into reserve pit. Liquids from pit will be allowed to evaporate. Formation water will be confined to storage tanks. Commercial contractor will handle sewage facilities, storage and disposal. Trash will be contained in trash baskets and hauled to an approved land fill.

ENVIRONMENTAL PARAMETERS

AFFECTED FLOODPLAINS AND/OR WETLANDS: None.

FLORA/FAUNA: A moderate cover of desert type vegetation consisting of black sagebrush, shadscale, curly mesquite and cheat grass occupies the site. Antelope, rabbits, small reptiles, birds and mammals. Sheep graze the area in the winter.

SOIL TYPE AND CHARACTERISTICS: Sandy loam surface with a moderate amount of surface stones.

EROSION/SEDIMENTATION/STABILITY: Little natural erosion. Sedimentation and stability are not a problem and location construction shouldn't cause an increase in stability or erosion problems. One small drainage begins within the location and will be covered with fill.

PALEONTOLOGICAL POTENTIAL: Survey completed by IPC on 9/26/05 and furnished for the file. The access road leading to the site will be moved 5 meters to avoid a formation which may contain paleontological resources.

RESERVE PIT

CHARACTERISTICS: 100' by 150' and 10' deep. The reserve pit is all within cut on the north east side of the location. A 15' wide bench is planned around the outer edges and 2' of freeboard.

LINER REQUIREMENTS (Site Ranking Form attached): Level 1 sensitivity. A 16 mil liner with a felt pad will be required for the reserve pit.

SURFACE RESTORATION/RECLAMATION PLAN

As per SITLA requirements.

SURFACE AGREEMENT:

As per SITLA requirements.

CULTURAL RESOURCES/ARCHAEOLOGY: Site was surveyed by MOAC on 10/03/05. A copy has been furnished to SITLA.

OTHER OBSERVATIONS/COMMENTS

Ben Williams of the UDWR stated that the area is classified as critical yearlong antelope range, however he did not recommend any stipulations, as water is the limiting factor affecting the population not forage. The UDWR database shows a red tailed hawk nest in ledges south and east of the location. It is not known if it has had recently activity. He suggested a restriction period from 4/1-7/15 for road and pad construction, drilling and workover rigs. If Westport desires any of these activities during that period, he will check the nest to see if is or has had recent activity.

This predrill investigation was conducted on a cool sunny day.

ATTACHMENTS

Photos of this site were taken and placed on file.

FLOYD BARTLETT
DOGM REPRESENTATIVE

02/23/06; 10:00 AM
DATE/TIME

**Evaluation Ranking Criteria and Ranking Score
For Reserve and Onsite Pit Liner Requirements**


<u>Site-Specific Factors</u>	<u>Ranking</u>	<u>Site Ranking</u>
Distance to Groundwater (feet)		
>200	0	
100 to 200	5	
75 to 100	10	
25 to 75	15	
<25 or recharge area	20	<u>0</u>
Distance to Surf. Water (feet)		
>1000	0	
300 to 1000	2	
200 to 300	10	
100 to 200	15	
< 100	20	
Distance to Nearest Municipal Well (feet)		
>5280	0	
1320 to 5280	5	
500 to 1320	10	
<500	20	<u>0</u>
Distance to Other Wells (feet)		
>1320	0	
300 to 1320	10	
<300	20	<u>10</u>
Native Soil Type		
Low permeability	0	
Mod. permeability	10	
High permeability	20	<u>10</u>
Fluid Type		
Air/mist	0	
Fresh Water	5	
TDS >5000 and <10000	10	
TDS >10000 or Oil Base Mud Fluid	15	
containing significant levels of hazardous constituents	20	<u>5</u>
Drill Cuttings		
Normal Rock	0	
Salt or detrimental	10	<u>0</u>
Annual Precipitation (inches)		
<10	0	
10 to 20	5	
>20	10	<u>0</u>
Affected Populations		
<10	0	
10 to 30	6	
30 to 50	8	
>50	10	<u>0</u>
Presence of Nearby Utility Conduits		
Not Present	0	
Unknown	10	
Present	15	<u>0</u>


Final Score 25 (Level I Sensitivity)

Sensitivity Level I = 20 or more; total containment is required.


Sensitivity Level I = 15-19; lining is discretionary.

Sensitivity Level II = below 15; no specific lining is required.





Casing Schematic



Well name:

03-06 Westport NBU 1021-13GOperator: **Westport Oil & Gas**String type: **Surface**

Project ID:

43-047-37723Location: **Uintah County, Utah****Design parameters:****Collapse**Mud weight: 8.400 ppg
Design is based on evacuated pipe.**Minimum design factors:****Collapse:**

Design factor 1.125

Burst:

Design factor 1.00

Environment:H2S considered? No
Surface temperature: 75 °F
Bottom hole temperature: 103 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 1,500 ft

Cement top: Surface

BurstMax anticipated surface
pressure: 1,760 psi
Internal gradient: 0.120 psi/ft
Calculated BHP 2,000 psi

No backup mud specified.

Tension:8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.50 (B)

Non-directional string.

Tension is based on buoyed weight.
Neutral point: 1,753 ft**Re subsequent strings:**Next setting depth: 9,400 ft
Next mud weight: 11.500 ppg
Next setting BHP: 5,616 psi
Fracture mud wt: 19.250 ppg
Fracture depth: 2,000 ft
Injection pressure 2,000 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	2000	9.625	32.30	H-40	ST&C	2000	2000	8.876	126.8
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	873	1370	1.570	2000	2270	1.14	57	254	4.49 J

Prepared by: Clinton Dworshak
Utah Div. of Oil & MiningPhone: (810) 538-5280
FAX: (801) 359-3940Date: March 7, 2006
Salt Lake City, Utah**Remarks:**Collapse is based on a vertical depth of 2000 ft, a mud weight of 8.4 ppg. The casing is considered to be evacuated for collapse purposes.
Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Engineering responsibility for use of this design will be that of the purchaser.

Well name:

03-06 Westport NBU 1021-13GOperator: **Westport Oil & Gas**String type: **Production**

Project ID:

43-047-37723Location: **Uintah County, Utah****Design parameters:****Collapse**Mud weight: 11.500 ppg
Design is based on evacuated pipe.**Minimum design factors:****Collapse:**

Design factor 1.125

Burst:

Design factor 1.00

Environment:H2S considered? No
Surface temperature: 75 °F
Bottom hole temperature: 207 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 1,500 ft

Cement top: Surface

BurstMax anticipated surface
pressure: 4,488 psi
Internal gradient: 0.120 psi/ft
Calculated BHP 5,616 psi

No backup mud specified.

Tension:8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.50 (B)

Non-directional string.

Tension is based on buoyed weight.
Neutral point: 7,784 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	9400	4.5	11.60	M-80	LT&C	9400	9400	3.875	217.9
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	5616	6350	1.131	5616	7780	1.39	90	267	2.96 B

Prepared by: Clinton Dworshak
Utah Div. of Oil & MiningPhone: (810) 538-5280
FAX: (801) 359-3940Date: March 7, 2006
Salt Lake City, Utah**Remarks:**

Collapse is based on a vertical depth of 9400 ft, a mud weight of 11.5 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Engineering responsibility for use of this design will be that of the purchaser.

From: Ed Bonner
To: Whitney, Diana
Date: 2/15/2006 3:57:43 PM
Subject: Well Clearance

The following wells have been given cultural resource clearance by the Trust Lands Cultural Resources Group:

EOG Resources, Inc
NBU 556-18E
NBU 557-18E

Summit Operating, LLC
State 16-32-13-22
State 8-32-13-22
State 6-36-13-22
State 4-36-13-22

Westport Oil & Gas Company
NBU 1021-28G
NBU 1021-28O (APD has name as **State 1021-28O**) One significant site which must be avoided
NBU 1021-13A
NBU 1021-13C
NBU 1021-13G
NBU 1021-13I
NBU 1021-13K
NBU 1021-13O

Wind River II Corporation
Snowshoe 2-15-16-22

If you have any questions regarding this matter please give me a call.

CC: Garrison, LaVonne; Hill, Brad; Hunt, Gil

United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, Utah 84145-0155

IN REPLY REFER TO:
3160
(UT-922)

March 2, 2006

Memorandum

To: Assistant District Manager Minerals, Vernal District

From: Michael Coulthard, Petroleum Engineer

Subject: 2006 Plan of Development Natural Buttes Unit Uintah County, Utah.

Pursuant to email between Diana Whitney, Division of Oil, Gas and Mining, and Mickey Coulthard, Utah State Office, Bureau of Land Management, the following wells are planned for calendar year 2006 within the Natural Buttes Unit, Uintah County, Utah.

API #	WELL NAME	LOCATION
-------	-----------	----------

(Proposed PZ Wasatch-MesaVerde)

43-047-37738	NBU 1022-19F	Sec 19 T10S R22E 2239 FNL 1622 FWL
43-047-37739	NBU 1022-19D	Sec 19 T10S R22E 0732 FNL 0640 FWL
43-047-37740	NBU 1022-19C	Sec 19 T10S R22E 0896 FNL 1891 FWL
43-047-37765	NBU 1022-16J	Sec 16 T10S R22E 2302 FSL 1901 FEL
43-047-37766	NBU 1022-16P	Sec 16 T10S R22E 0724 FSL 0973 FEL
43-047-37767	NBU 1022-16L	Sec 16 T10S R22E 1904 FSL 0343 FWL
43-047-37768	NBU 1022-18H	Sec 18 T10S R22E 1947 FNL 0465 FEL
43-047-37769	NBU 1022-18G	Sec 18 T10S R22E 1870 FNL 1383 FEL
43-047-37770	NBU 1022-18I	Sec 18 T10S R22E 1592 FSL 0803 FEL
43-047-37771	NBU 1022-18E	Sec 18 T10S R22E 1656 FNL 0606 FWL
43-047-37772	NBU 1022-18J	Sec 18 T10S R22E 2158 FSL 2171 FEL
43-047-37773	NBU 1022-18N	Sec 18 T10S R22E 0125 FSL 1249 FWL
43-047-37774	NBU 1022-18B	Sec 18 T10S R22E 0818 FNL 2040 FEL
43-047-37775	NBU 1022-18P	Sec 18 T10S R22E 0169 FSL 0249 FEL
43-047-37776	NBU 1022-18D	Sec 18 T10S R22E 0765 FNL 0311 FWL
43-047-37777	NBU 1022-18O	Sec 18 T10S R22E 0134 FSL 2445 FEL
43-047-37783	NBU 1022-19K	Sec 19 T10S R22E 1509 FSL 1427 FWL
43-047-37778	NBU 1022-19H	Sec 19 T10S R22E 2298 FNL 1086 FEL
43-047-37779	NBU 1022-19B	Sec 19 T10S R22E 0696 FNL 2180 FEL
43-047-37780	NBU 1022-19G	Sec 19 T10S R22E 2069 FNL 2241 FEL
43-047-37781	NBU 1022-19I	Sec 19 T10S R22E 2135 FSL 0460 FEL
43-047-37782	NBU 1022-19O	Sec 19 T10S R22E 0740 FSL 2065 FEL
43-047-37734	NBU 1021-27E	Sec 27 T10S R21E 1862 FNL 0535 FWL
43-047-37728	NBU 1021-28G	Sec 28 T10S R21E 1952 FNL 1971 FEL
43-047-37721	NBU 1021-13C	Sec 13 T10S R21E 0576 FNL 1772 FWL
43-047-37722	NBU 1021-13A	Sec 13 T10S R21E 0651 FNL 1311 FEL

Page 2

43-047-37723 NBU 1021-13G	Sec 13 T10S R21E 1444 FNL 2651 FEL
43-047-37724 NBU 1021-13K	Sec 13 T10S R21E 1935 FSL 1486 FWL
43-047-37725 NBU 1021-13I	Sec 13 T10S R21E 2353 FSL 0668 FEL
43-047-37727 NBU 1021-13O	Sec 13 T10S R21E 0777 FSL 1573 FEL
43-047-37761 NBU 920-20P	Sec 20 T09S R20E 0769 FSL 0978 FEL
43-047-37760 NBU 920-20O	Sec 20 T09S R20E 0842 FSL 1913 FEL
43-047-37759 NBU 920-20N	Sec 20 T09S R20E 0803 FSL 1885 FWL
43-047-37758 NBU 920-20M	Sec 20 T09S R20E 0630 FSL 0838 FWL
43-047-37757 NBU 920-20L	Sec 20 T09S R20E 2104 FSL 0827 FWL
43-047-37756 NBU 920-20J	Sec 20 T09S R20E 1466 FSL 1653 FEL
43-047-37755 NBU 920-20I	Sec 20 T09S R20E 1955 FSL 0717 FEL
43-047-37732 NBU 920-22E	Sec 22 T09S R20E 2009 FNL 0756 FWL
43-047-37764 NBU 920-24M	Sec 24 T09S R20E 0614 FSL 0851 FWL
43-047-37753 NBU 920-14M	Sec 14 T09S R20E 0536 FSL 0612 FWL
43-047-37754 NBU 920-14N	Sec 14 T09S R20E 0732 FSL 1805 FWL

This office has no objection to permitting the wells at this time.

/s/ Michael L. Coulthard

bcc: File – Natural Buttes Unit
Division of Oil Gas and Mining
Central Files



State of Utah

**Department of
Natural Resources**

MICHAEL R. STYLER
Executive Director

**Division of
Oil, Gas & Mining**

JOHN R. BAZA
Division Director

JON M. HUNTSMAN, JR.
Governor

GARY R. HERBERT
Lieutenant Governor

March 15, 2006

Westport Oil & Gas Company, LP
1368 S 1200 E
Vernal, UT 84078

Re: Natural Buttes Unit 1021-13G Well, 1444' FNL, 2651' FEL, SW NE, Sec. 13,
T. 10 South, R. 21 East, Uintah County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-047-37723.

Sincerely,

Gil Hunt
Associate Director

pab
Enclosures

cc: Uintah County Assessor
SITLA
Bureau of Land Management, Vernal District Office

Operator: Westport Oil & Gas Company, LP
Well Name & Number Natural Buttes Unit 1021-13G
API Number: 43-047-37723
Lease: ML-23608

Location: SW NE Sec. 13 T. 10 South R. 21 East

Conditions of Approval

1. **General**

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

2. **Notification Requirements**

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- 24 hours prior to cementing or testing casing
- 24 hours prior to testing blowout prevention equipment
- 24 hours prior to spudding the well
- within 24 hours of any emergency changes made to the approved drilling program
- prior to commencing operations to plug and abandon the well

The following are Division of Oil, Gas and Mining contacts and their work telephone numbers (please leave a voice mail message if the person is not available to take the call):

- Dan Jarvis at (801) 538-5338
- Carol Daniels at (801) 538-5284 (spud)

3. **Reporting Requirements**

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

4. Compliance with the State of Utah Antiquities Act forbids disturbance of archeological, historical, or paleontological remains. Should archeological, historical or paleontological remains be encountered during your operations, you are required to immediately suspend all operations and immediately inform the Trust Lands Administration and the Division of State History of the discovery of such remains.

5. Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis. (Copy Attached)

Page 2

43-047-37723

March 15, 2006

6. In accordance with Order in Cause No. 190-5(b) dated October 28, 1982, the Operator shall comply with requirements of Rules R649-3-31 and R649-3-27 pertaining to Designated Oil Shale Areas. Additionally, the operator shall ensure that the surface and/or production casing is properly cemented over the entire oil shale interval as defined by Rule R649-3-31. The Operator shall report the actual depth the oil shale is encountered to the Division.
7. Surface casing shall be cemented to the surface.

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-23608
2. NAME OF OPERATOR: WESTPORT OIL & GAS COMPANY L.P.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: NATURAL BUTTES UNIT
3. ADDRESS OF OPERATOR: 1368 S. 1200 E. CITY VERNAL STATE UT ZIP 84078		8. WELL NAME and NUMBER: NBU 1021-13G
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1444'FNL, 2651'FEL		9. API NUMBER: 43-047-37723
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNE 13 10S 21E		10. FIELD AND POOL, OR WILDCAT: NATURAL BUTTES
COUNTY: UINTAH		STATE: UTAH


11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: PIPELINE CHANGE
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

THE OPERATOR REQUESTS AUTHORIZATION TO CHANGE THE EXISTING PIPELINE PROPOSED IN THE ORIGINAL APD. AN ON-SITE WAS CONDUCTED ON 02/23/2006 WITH THE UTDGDM REPRESENTATIVE. WHILE CONDUCTING THE ON-SITE INSPECTION IT WAS DECIDED TO CHANGE THE PIPELINE TO A TOTAL OF APPROXIMATELY 50' +/- OF PIPELINE IS PROPOSED.

PLEASE REFER TO THE ATTACHED TOPO MAP D.

NAME (PLEASE PRINT) SHEILA UPCHEGO	TITLE REGULATORY ANALYST
SIGNATURE 	DATE 3/13/2006

(This space for State use only)

(5/2000)

Accepted by the
Utah Division of
Oil, Gas and Mining


FOR RECORD ONLY

Approval should be obtained from appropriate land management Agency/owner

RECEIVED

MAR 23 2006

DIV. OF OIL, GAS & MINING



APPROXIMATE TOTAL PIPELINE DISTANCE = 50' +/-

LEGEND:

- PROPOSED ACCESS ROAD
- EXISTING PIPELINE
- PROPOSED PIPELINE
- PROPOSED PIPELINE (SERVICING OTHER WELLS)



Kerr-McGee Oil & Gas Onshore LP

NBU #1021-13G
SECTION 13, T10S, R21E, S.L.B.&M.
1444' FNL 2651' FEL



Utah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813

**TOPOGRAPHIC
MAP**

01 14 06
 MONTH DAY YEAR

SCALE: 1" = 2000' DRAWN BY: C.P. REVISED: 03-07-06



Division of Oil, Gas and Mining
OPERATOR CHANGE WORKSHEET

ROUTING

1. DJJ

2. CDW

X Change of Operator (Well Sold)

Operator Name Change/Merger

The operator of the well(s) listed below has changed, effective:

1/6/2006

FROM: (Old Operator):

N2115-Westport Oil & Gas Co., LP
 1368 South 1200 East
 Vernal, UT 84078

Phone: 1-(435) 781-7024

TO: (New Operator):

N2995-Kerr-McGee Oil & Gas Onshore, LP
 1368 South 1200 East
 Vernal, UT 84078

Phone: 1-(435) 781-7024

CA No.

Unit:

NATURAL BUTTES UNIT

WELL NAME

SEC TWN RNG

API NO

ENTITY

LEASE

WELL

WELL

NO

TYPE

TYPE

STATUS

OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

1. (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 5/10/2006
2. (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 5/10/2006
3. The new company was checked on the **Department of Commerce, Division of Corporations Database** on: 3/7/2006
- 4a. Is the new operator registered in the State of Utah: YES Business Number: 1355743-0181
- 4b. If **NO**, the operator was contacted on: _____
- 5a. (R649-9-2) Waste Management Plan has been received on: IN PLACE
- 5b. Inspections of LA PA state/fee well sites complete on: n/a 3 LA wells & all PA wells transferred
- 5c. Reports current for Production/Disposition & Sundries on: ok
6. **Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM 3/27/2006 BIA not yet
7. **Federal and Indian Units:**
 The BLM or BIA has approved the successor of unit operator for wells listed on: 3/27/2006
8. **Federal and Indian Communization Agreements ("CA"):**
 The BLM or BIA has approved the operator for all wells listed within a CA on: n/a
9. **Underground Injection Control ("UIC")** The Division has approved UIC Form 5, Transfer of Authority to **Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: _____

DATA ENTRY:

1. Changes entered in the **Oil and Gas Database** on: 5/15/2006
2. Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 5/15/2006
3. Bond information entered in RBDMS on: 5/15/2006
4. Fee/State wells attached to bond in RBDMS on: 5/16/2006
5. Injection Projects to new operator in RBDMS on: _____
6. Receipt of Acceptance of Drilling Procedures for APD/New on: n/a Name Change Only

BOND VERIFICATION:

1. Federal well(s) covered by Bond Number: CO1203
2. Indian well(s) covered by Bond Number: RLB0005239
3. (R649-3-1) The **NEW** operator of any fee well(s) listed covered by Bond Number RLB0005236
- a. The **FORMER** operator has requested a release of liability from their bond on: n/a rider added KMG
- The Division sent response by letter on: _____

LEASE INTEREST OWNER NOTIFICATION:

4. (R649-2-10) The **FORMER** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: 5/16/2006

COMMENTS:

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.

FORM APPROVED
OMB No. 1004-0135
Expires November 30, 2000

5. Lease Serial No.

MULTIPLE LEASES

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.

MUTIPLE WELLS

9. API Well No.

10. Field and Pool, or Exploratory Area

11. County or Parish, State

UINTAH COUNTY, UTAH

SUBMIT IN TRIPLICATE - Other instructions on reverse side

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

KERR-McGEE OIL & GAS ONSHORE LP

3a. Address

1368 SOUTH 1200 EAST VERNAL, UT 84078

3b. Phone No. (include area code)

(435) 781-7024

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

SEE ATTACHED

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other CHANGE OF OPERATOR
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.

PLEASE BE ADVISED THAT KERR-McGEE OIL & GAS ONSHORE LP, IS CONSIDERED TO BE THE OPERATOR OF THE ATTACHED WELL LOCATIONS. EFFECTIVE JANUARY 6, 2006.

KERR-McGEE OIL & GAS ONSHORE LP, IS RESPONSIBLE UNDER TERMS AND CONDITIONS OF THE LEASE(S) FOR THE OPERATIONS CONDUCTED UPON LEASE LANDS. BOND COVERAGE IS PROVIDED BY STATE OF UTAH NATIONWIDE BOND NO. RLB0005237.

RECEIVED

MAY 10 2006

DIV. OF OIL, GAS & MINING

BLM BOND = C01203

BIA BOND = RLB0005237

APPROVED 5/16/06

Earlene Russell

Division of Oil, Gas and Mining
Earlene Russell, Engineering Technician

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed)

RANDY BAYNE

Title

DRILLING MANAGER

Signature

Date

May 9, 2006

THIS SPACE FOR FEDERAL OR STATE USE

Approved by

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on reverse)

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0135
Expires November 30, 2000

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.

5. Lease Serial No.

MULTIPLE LEASES

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.

MUTIPLE WELLS

9. API Well No.

10. Field and Pool, or Exploratory Area

11. County or Parish, State

UINTAH COUNTY, UTAH

SUBMIT IN TRIPLICATE - Other instructions on reverse side

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

WESTPORT OIL & GAS COMPANY L.P.

3a. Address

1368 SOUTH 1200 EAST VERNAL, UT 84078

3b. Phone No. (include area code)

(435) 781-7024

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

SEE ATTACHED

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other CHANGE OF OPERATOR
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.

EFFECTIVE JANUARY 6, 2006, WESTPORT OIL & GAS COMPANY L.P., HAS RELINQUISHED THE OPERATORSHIP OF THE ATTACHED WELL LOCATIONS TO KERR-McGEE OIL & GAS ONSHORE LP.

APPROVED 5/16/06
Earlene Russell
Division of Oil, Gas and Mining
Earlene Russell, Engineering Technician

RECEIVED
MAY 10 2006

DIV. OF OIL, GAS & MINING

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed)

BRAD LANEY

Title

ENGINEERING SPECIALIST

Signature

Date

May 9, 2006

THIS SPACE FOR FEDERAL OR STATE USE

Approved by

Brad Laney

Title

Date

5-9-06

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on reverse)

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals Use APPLICATION FOR PERMIT TO DRILL form for such proposals

1 TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5 LEASE DESIGNATION AND SERIAL NUMBER ML-23608
2 NAME OF OPERATOR KERR MCGEE OIL AND GAS ONSHORE LP		6 IF INDIAN, ALLOTTEE OR TRIBE NAME NATURAL BUTTES UNIT
3 ADDRESS OF OPERATOR 1368 S 1200 E CITY VERNAL STATE UT ZIP 84078		7 UNIT or CA AGREEMENT NAME NATURAL BUTTES UNIT
4 LOCATION OF WELL FOOTAGES AT SURFACE 1444' FNL 2651' FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN SWNE 13 10S 21E		8 WELL NAME and NUMBER NBU 1021-13G
5 PHONE NUMBER (435) 781-7003		9 API NUMBER 4304737723
6 COUNTY UINTAH		10 FIELD AND POOL, OR WILDCAT NATURAL BUTTES
7 STATE UTAH		

11 CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION		TYPE OF ACTION	
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start _____	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> DEEPEN <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> PLUG BACK <input type="checkbox"/> PRODUCTION (START/RESUME) <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	<input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> TEMPORARILY ABANDON <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> WATER SHUT-OFF <input checked="" type="checkbox"/> OTHER <u>APD EXTENSION</u>
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion _____			

12 DESCRIBE PROPOSED OR COMPLETED OPERATIONS Clearly show all pertinent details including dates, depths, volumes, etc

THE OPERATOR REQUESTS AUTHORIZATION FOR A ONE YEAR EXTENSION FOR THE SUBJECT WELL LOCATION SO THAT THE DRILLING OPERATIONS MAY BE COMPLETED. THE ORIGINAL APD WAS APPROVED BY THE DIVISION OF OIL, GAS AND MINING ON MARCH 15, 2006

Approved by the
Utah Division of
Oil, Gas and Mining

Date: 02-21-07
By: [Signature]

COPY SENT TO OPERATOR
Date: 2-22-07
Time: 2 PM

NAME (PLEASE PRINT) RAMEY HOOPES	TITLE REGULATORY CLERK
SIGNATURE [Signature]	DATE 2/8/2007

(This space for State use only)

RECEIVED
FEB 20 2007
DIV. OF OIL, GAS & MINING

**Application for Permit to Drill
Request for Permit Extension
Validation**

(this form should accompany the Sundry Notice requesting permit extension)

API: 4304737723
Well Name: NBU 1021-13G
Location: SWNE, SEC 13-T10S-R21E
Company Permit Issued to: KERR MCGEE OIL AND GAS ONSHORE LP
Date Original Permit Issued: 3/15/2006

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision.

Following is a checklist of some items related to the application, which should be verified.

If located on private land, has the ownership changed, if so, has the surface agreement been updated? Yes ☐ No ☒

Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? Yes ☐ No ☒

Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? Yes ☐ No ☒

Have there been any changes to the access route including ownership, or right-of-way, which could affect the proposed location? Yes ☐ No ☒

Has the approved source of water for drilling changed? Yes ☐ No ☒

Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? Yes ☐ No ☒

Is bonding still in place, which covers this proposed well? Yes ☒ No ☐

Ramey Hooper
Signature

2/8/2007

Date

Title: Regulatory Clerk

Representing: Kerr McGee Oil & Gas Onshore LP

RECEIVED
FEB 20 2007
DIV. OF OIL, GAS & MINING

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 6

ENTITY ACTION FORM

Operator: KERR McGEE OIL & GAS ONSHORE LP Operator Account Number: N 2995
Address: 1368 SOUTH 1200 EAST
city VERNAL
state UT zip 84078 Phone Number: (435) 781-7024

Well 1

API Number	Well Name		QQ	Sec	Twp	Rng	County
4304737723	NBU 1021-13G		SWNE	13	10S	21E	UINTAH
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
B	99999	2900	11/27/2007			11/29/07	
Comments: MIRU PETE MARTIN BUCKET RIG. <i>WSMVD</i> SPUD WELL LOCATION ON 11/27/2007 AT 1100 HRS.							

Well 2

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
Comments:							

Well 3

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
Comments:							

ACTION CODES:

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

SHEILA UPCHEGO

Name (Please Print)

Signature

SENIOR LAND SPECIALIST

Title

11/28/2007

Date

RECEIVED

NOV 28 2007

DIV. OF OIL, GAS & MINING

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-2608
2. NAME OF OPERATOR: KERR MCGEE OIL & GAS ONSHORE LP		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 1368 SOUTH 1200 EAST CITY VERNAL STATE UT ZIP 84078		7. UNIT or CA AGREEMENT NAME: UNIT #891008900A
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1444'FNL, 2651'FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNE 13 10S 21E		8. WELL NAME and NUMBER: NBU 1021-13G
PHONE NUMBER: (435) 781-7024		9. API NUMBER: 4304737723
		10. FIELD AND POOL, OR WILDCAT: NATURAL BUTTES
		COUNTY: UINTAH
		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON	
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE	
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL	
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: WELL SPUD	
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION		

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

MIRU PETE MARTIN BUCKET RIG. DRILLED 20" CONDUCTOR HOLE TO 40'. RAN 14" 36.7# SCHEDULE 10 PIPE. CMT W/28 SX READY MIX.

SPUD WELL LOCATION ON 11/27/2007 AT 1100 HRS.

RECEIVED
DEC 03 2007

DIV. OF OIL, GAS & MINING

NAME (PLEASE PRINT) SHEILA UPCHEGO	TITLE SENIOR LAND ADMIN SPECIALIST
SIGNATURE 	DATE 11/28/2007

(This space for State use only)

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL	OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____	5. LEASE DESIGNATION AND SERIAL NUMBER: ML-2608
2. NAME OF OPERATOR:	KERR McGEE OIL & GAS ONSHORE LP	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR:	1368 SOUTH 1200 EAST CITY VERNAL STATE UT ZIP 84078	7. UNIT or CA AGREEMENT NAME: UNIT #891008900A
4. LOCATION OF WELL	FOOTAGES AT SURFACE: 1444'FNL, 2651'FEL	8. WELL NAME and NUMBER: NBU 1021-13G
	QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNE 13 10S 21E	9. API NUMBER: 4304737723
		10. FIELD AND POOL, OR WILDCAT: NATURAL BUTTES
		COUNTY: UINTAH
		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: SET SURFACE CSG.
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.


MIRU BILL MARTIN AIR RIG ON 12/01/2007. DRILLED 12 1/4" SURFACE HOLE TO 2220'. RAN 9 5/8" 36# J-55 SURFACE CSG. LEAD CMT W/300 SX PREM CLASS G @15.8 PPG 1.15 YIELD. TAILED CMT W/150 SX PREM CLASS G @15.8 PPG 1.15 YIELD. NO RETURNS TO PIT. TOP OUT W/225 SX PREM CLASS G @15.8 PPG 1.15 YIELD. DOWN BACKSIDE. WOC. 2ND TOP OUT W/125 SX PREM CLASS G @15.8 PPG 1.15 YIELD. DOWN BACKSIDE GOOD CMT TO SURFACE HOLE STAYED FULL.

WORT.

RECEIVED

DEC 14 2007

DIV. OF OIL, GAS & MINING

NAME (PLEASE PRINT)	SHEILA UPCHEGO	TITLE	SENIOR LAND ADMIN SPECIALIST
SIGNATURE		DATE	12/11/2007

(This space for State use only)

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.


1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-2608
2. NAME OF OPERATOR: KERR McGEE OIL & GAS ONSHORE LP		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 1368 SOUTH 1200 EAST CITY VERNAL STATE UT ZIP 84078		7. UNIT or CA AGREEMENT NAME: UNIT #891008900A
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1444'FNL, 2651'FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNE 13 10S 21E		8. WELL NAME and NUMBER: NBU 1021-13G
		9. API NUMBER: 4304737723
		10. FIELD AND POOL, OR WILDCAT: NATURAL BUTTES
		COUNTY: UINTAH
		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: FINAL DRILLING OPERATIONS
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

FINISHED DRILLING FROM 2220' TO 9131' ON 12/20/2007. RAN 4 1/2" 11.6# I-80 PRODUCTION CSG. LEAD CMT W/310 SX PREM LITE II @11.0 PPG 3.38 YIELD. TAILED CMT W/1225 SX 50/50 POZ @14.3 PPG 1.31 YIELD. GOOD RETURNS THROUGHOUT JOB N/ND BOPE & SET SLIPS ON 4 1/2" PROD CSG ROUGH CUT CSG. L/OUT SAME CLEAN MUD TANKS.

RELEASED ENSIGN RIG 12 ON 12/23/2007 AT 1800 HRS.

NAME (PLEASE PRINT) SHEILA UPCHEGO	TITLE SENIOR LAND ADMIN SPECIALIST
SIGNATURE 	DATE 12/26/2007

(This space for State use only)

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____	5. LEASE DESIGNATION AND SERIAL NUMBER: ML-2608
2. NAME OF OPERATOR: KERR MCGEE OIL & GAS ONSHORE LP	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 1368 SOUTH 1200 EAST CITY VERNAL STATE UT ZIP 84078	7. UNIT or CA AGREEMENT NAME: UNIT #891008900A
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1444'FNL, 2651'FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNE 13 10S 21E	8. WELL NAME and NUMBER: NBU 1021-13G
	9. API NUMBER: 4304737723
	10. FIELD AND POOL, OR WILDCAT: NATURAL BUTTES
	COUNTY: UINTAH
	STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: <u>PRODUCTION</u>
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	<u>START-UP</u>

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.


THE SUBJECT WELL LOCATION WAS PLACED ON PRODUCTION ON 02/02/2004 AT 10:00 AM.

PLEASE REFER TO THE ATTACHED CHRONOLOGICAL WELL HISTORY.

RECEIVED

FEB 25 2008

DIV. OF OIL, GAS & MINING

NAME (PLEASE PRINT) SHEILA UPCHEGO	TITLE SENIOR LAND ADMIN SPECIALIST
SIGNATURE 	DATE 2/4/2008

(This space for State use only)



Anadarko Petroleum Corporation
1368 South 1200 East
Vernal, UT 84078

CHRONOLOGICAL WELL HISTORY

NBU 1021-13G

LOCATION SWNE, SEC.13, T10S, R21E
UINTAH COUNTY, UT

DATE	ACTIVITY	STATUS
11/01/07	LOCATION STARTED ENSIGN 12	
11/26/07	LOCATION COMPLETED ENSIGN 12	P/L IN, WOBR
11/27/07	SET CONDUCTOR ENSIGN 12	WOAR
12/01/07	SET AIR RIG ENSIGN 12	BUILDING
12/10/07	9-5/8" @ 2164' ENSIGN 12	WORT
12/12/07	TD: 2220' Csg. 9 5/8"@ 2164' MW: 8.4 RURT.	SD: 12/xx/07 DSS: 0
12/13/07	TD: 2220' Csg. 9 5/8"@ 2164' MW: 8.4 RURT. NU and test BOPE. PU BHA @ report time.	SD: 12/xx/07 DSS: 0
12/14/07	TD: 3145' Csg. 9 5/8"@ 2164' MW: 8.8 PU BHA and drill FE. Rotary spud @ 1530 hrs 12/13/07. Drill from 2220'-3145'. DA @ report time.	SD: 12/13/07 DSS: 1
12/17/07	TD: 6614' Csg. 9 5/8"@ 2164' MW: 9.8 Drill from 3145'-6614'. DA @ report time.	SD: 12/13/07 DSS: 4
12/18/07	TD: 7005' Csg. 9 5/8"@ 2164' MW: 10.0 Drill from 6614'-6942'. TFNB. Drill to 7005'. DA @ report time.	SD: 12/13/07 DSS: 5
12/19/07	TD: 7964' Csg. 9 5/8"@ 2164' MW: 10.3 Drill from 7005'-7964'. DA @ report time.	SD: 12/13/07 DSS: 6
12/20/07	TD: 8692' Csg. 9 5/8"@ 2164' MW: 10.7 Drill from 7964'-8692'. TFNB @ report time.	SD: 12/13/07 DSS: 7
12/21/07	TD: 9131' Csg. 9 5/8"@ 2164' MW: 11.1 TFNB. Drill from 8692'-9131'. CCH and prep for short trip @ report time.	SD: 12/13/07 DSS: 8

12/24/07

TD: 9131' Csg. 9 5/8" @ 2164' MW: 11.5 SD: 12/13/07 DSS: 12
Short trip and raise MW to 11.5 w/ 5% LCM. TOOH and run logs to TD. TIH, CCH, and LDDS.
Run and cmt 4.5" prod csg. Land hanger, ND, clean pits, and release rig @ 1800 hrs on 12/23.
RDRT @ report time. Move scheduled for 12/26.

12/26/07

TD: 9131' Csg. 9 5/8" @ 2164' MW: 11.5 SD: 12/13/07 DSS: 12
Move rig to NBU 1021-13A @ report time.

01/28/08

RIH W/ TBG

Days On Completion: 1

Remarks: HSM. ROAD RIG FROM NBU 922-33H4 TO THE NBU 1021-13G. SPOT IN RIG
EQUIPMENT & RU RIG. PU 3 7/8" MILL & SUB. DRIFT & TALLY 4 JTS OF 2 3/8" J-55 4.7#
TUBING. EOT @ 126' WINTERIZE WELL HEAD. SWI SDFN. DUE TO HIGH WIND NOT
ABLE TO PU TUBING

01/29/08

PREP TO FRAC

Days On Completion: 2

Remarks: DAY 2) HSM. PU DRIFT & TALLY 230 JTS OF 2 3/8" J-55 4.7# TUBING W/ 3 7/8"
MILL & SUB. EOT @ 7,240'. POOH W/ 115 STANDS. ND BOP'S NU FRAC VALVES. MIRU
B&C QUICK TEST & CUTTERS TO PRESSURE TEST & PERFORATE. PRESSURE TEST
CASING & BOTH FRAC VALVES TO 7,500 PSI. GOOD TEST. RDMO B&C QUICK TEST. RIH
W/ 3 3/8" EXP GNS, 23 GRM, .36 HOLES, 90 DEG PHASING. PERF 8,894' - 8,904' 4 SPF, 40
HOLES. WINTERIZE WELL HEAD. SWI SDFN

01/30/08

FRAC

Days On Completion: 3

Remarks: DAY 3) HSM. MIRU BJ & CUTTERS TO FRAC & PERFORATE. PRIME UP PUMPS
& LINES. PRESSURE TEST TO 8,000 PSI.

STG 1) WHP 1,329 PSI, BRK 5,354 PSI @ 6.3 BPM, ISIP 2,732 PSI, FG .74 PUMP 100 BBLS
@ 50.0 BPM @ 5,150 PSI = 40 OF 40 HOLES OPEN. MP 6,840 PSI, MR 52.0 BPM, AP 5,525
PSI, AR 51.0 BPM, ISIP 3,029 PSI, FG .77 NPI 297 PSI, PUMP 1,142 BBLS SLICK WATER &
31,432 LBS OF 30/50 SAND & 5,000 LBS OF 20/40 RESIN COATED SAND, TOTAL PROP
PUMPED 35,432 LBS

STG 2) RIH W/ 3 3/8" EXP GNS, 23 GRM, .36 HOLES, 90 & 180 DEG PHASING. SET 8K
BAKER CBP @ 8,629', PERF 8,594' - 99' 4 SPF, 8,528' - 30' 4 SPF, 8,492' - 94' 4 SPF,
8,432' - 34' 2 SPF, 40 HOLES WHP 143 PSI, BRK 4,836 PSI @ 6.3 BPM, ISIP 3,001 PSI,
FG .79 PUMP 100 BBLS @ 50.7 BPM @ 5,520 PSI = 36 OF 40 HOLES OPEN. MP 5,729 PSI,
MR 52.5 BPM, AP 4,479 PSI, AR 51.0 BPM, ISIP 2,536 PSI, FG .73 NPI -465 PSI, PUMP
1,876 BBLS SLICK WATER & 62,571 LBS OF 30/50 SAND & 5,000 LBS OF 20/40 RESIN
COATED SAND, TOTAL PROP PUMPED 67,571 LBS

STG 3) RIH W/ 3 3/8" EXP GNS, 23 GRM, .36 HOLES, 90 DEG PHASING. SET 8K BAKER
CBP @ 8,306', PERF 8,263' - 69' 4 SPF, 8,144' - 48' 4 SPF, 40 HOLES WHP 65 PSI, BRK
3,842 PSI @ 6.3 BPM, ISIP 2,076 PSI, FG .69 PUMP 100 BBLS @ 51.7 BPM @ 4,520 PSI =
40 OF 40 HOLES OPEN. MP 4,756 PSI, MR 53.0 BPM, AP 3,836 PSI, AR 52.0 BPM, ISIP
2,069 PSI, FG .69 NPI -7 PSI, PUMP 1,140 BBLS SLICK WATER & 33,928 LBS OF 30/50
SAND & 5,000 LBS OF 20/40 RESIN COATED SAND, TOTAL PROP PUMPED 38,928 LBS

STG 4) RIH W/ 3 3/8" EXP GNS, 23 GRM, .36 HOLES, 120 DEG PHASING. SET 8K BAKER
CBP @ 7,894', PERF 7,852' - 64' 3 SPF, 36 HOLES WHP 277 PSI, BRK 4,350 PSI @ 6.3
BPM, ISIP 1,772 PSI, FG .66 PUMP 100 BBLS @ 52.0 BPM @ 4,240 PSI = 36 OF 36 HOLES
OPEN. MP 4,756 PSI, MR 52.5 BPM, AP 3,975 PSI, AR 52.0 BPM, ISIP 2,284 PSI, FG .73

NPI 512 PSI, PUMP 1,189 BBLS SLICK WATER & 41,184 LBS OF 30/50 SAND & 5,000 LBS OF 20/40 RESIN COATED SAND, TOTAL PROP PUMPED 46,184 LBS

WINTERIZE WELL HEAD. SWI SDFN

01/31/08

FRAC

Days On Completion: 4

Remarks: DAY 4) HSM. CUTTERS TO FRAC & PERFORATE. PRIME UP PUMPS & LINES. PRESSURE TEST TO 8,000 PSI.

STG 5) RIH W/ 3 3/8" EXP GNS, 23 GRM, .36 HOLES, 90 DEG PHASING. SET 8K BAKER CBP @ 7,755', PERF 7,720' - 25' 4 SPF, 7,642' - 46' 4 SPF, 7,580' - 82' 4 SPF, 7,522' - 23' 4 SPF, 40 HOLES WHP 220 PSI, BRK 4,692 PSI @ 6.3 BPM, ISIP 1635 PSI, FG .65 PUMP 100 BBLS @ 52.5 BPM @ 4,100 PSI = 40 OF 40 HOLES OPEN. MP 4,597 PSI, MR 53.0 BPM, AP 3,694 PSI, AR 52.5 BPM, ISIP 2,397 PSI, FG .75 NPI 762 PSI, PUMP 4,814 BBLS SLICK WATER & 174,392 LBS OF 30/50 SAND & 5,000 LBS OF 20/40 RESIN COATED SAND, TOTAL PROP PUMPED 179,392 LBS

STG 6) RIH W/ 3 3/8" EXP GNS, 23 GRM, .36 HOLES, 90 DEG PHASING. SET 8K BAKER CBP @ 7,350', PERF 7,310' - 20' 4 SPF, 40 HOLES WHP 175 PSI, BRK 5,792 PSI @ 6.3 BPM, ISIP 2,028 PSI, FG .72 PUMP 100 BBLS @ 52.0 BPM @ 4,702 PSI = 36 OF 40 HOLES OPEN MP 5,236 PSI, MR 52.0 BPM, AP 4,694 PSI, AR 51.5 BPM, ISIP 2,698 PSI, FG .81 NPI 670 PSI, PUMP 560 BBLS SLICK WATER & 13,253 LBS OF 30/50 SAND & 5,000 LBS OF 20/40 RESIN COATED SAND, TOTAL PROP PUMPED 18,253 LBS

KILL PLG) RIH SET 8K BAKER CBP @ 7,350' RDMO BJ & CUTTERS. ND FRAC VALVES NU BOP'S. PU 3 7/8" BIT FAST EDDIE POBS & SN. RIH W/ 230 JTS OF 2 3/8" J-55 4.7# TBG. EOT @ 7,240' POOH W/ 2 STAND TO DROP WATER LEVEL @ SURFACE. EOT @ 7,114'. WINTERIZE WELL HEAD. SWI SDFN.

02/01/08

DRILL CBP'S

Days On Completion: 5

Remarks: DAY 5) HSM. PU 4 JTS. RU POWER SWIVEL & RU RIG PUMP. BRK CIRCULATION W/ 2% KCL WATER. RIH. C/O 5' OF SAND TAG PLG 1 @ 7,260' DRL PLG IN 10 MIN 100 PSI INCREASE RIH C/O 30' OF SAND TAG PLG 2 @ 7,352' DRL PLG IN 10 MIN 800 PSI INCREASE RIH C/O 30' OF SAND TAG PLG 3 @ 7,755' DRL PLG IN 10 MIN 200 PSI INCREASE RIH C/O 30' OF SAND TAG PLG 4 @ 7,894' DRL PLG IN 10 MIN 400 PSI INCREASE RIH C/O 30' OF SAND TAG PLG 5 @ 8,306' DRL PLG IN 10 MIN 300 PSI INCREASE RIH C/O 30' OF SAND TAG PLG 6 @ 8,620' DRL PLG IN 10 MIN 200 PSI INCREASE RIH C/O TO 9,000' CIRCULATE WELL CLEAN. RD POWER SWIVEL. POOH LD 49 JTS OF 2 3/8" J-55 4.7# TBG. LAND TUBING W/ 237 JTS. EOT & 7,667.10'. ND BOP'S NU WELL HEAD. DROP BALL TO SHEAR OFF BIT. PUMP OFF BIT @ 1,850 PSI. SWI FOR 30 MINUTES SO BIT CAN FALL TO BOTTOM. TURN WELL OVER TO FLOW TESTERS

298 JTS OUTBOUND TLTR	10,721 BBLS KB	15.00'
237 JTS LANDED RIG REC	3,000 BBLS HANGER	.83'
61 JTS RETURNED LLTR	7,721 BBLS TUBING (237 JTS)	7,449.07'
XN NIPPLE	2.20'	
LANDED	7,671.10'	

02/02/08

FLOWBACK REPORT: CP 1600#, TP 1200#, CK 20/64", 60 BWPH, LOAD REC'D 4060 BBLS, REMAINING LTR 6661 BBLS

02/03/08

FLOWBACK REPORT: CP 2350#, TP 1300#, CK 20/64", 45 BWPH, LOAD REC'D 1170 BBLS, REMAINING LTR 5491 BBLS

WENT ON SALES: @ 10:00 AM, 504 MCF, 1250 TBG, 2450 CSG, 20/64 CK, 40 BBWH

ON SALES: 0 MCF, 0 BC, 1080 BW, TP: 2350#, CP: 1300#, 20/64 CHK, 24HRS, LP: 0#.

02/04/08

FLOWBACK REPORT: CP 2950#, TP 1500#, CK 20/64", 25 BWPH, LOAD REC'D 795 BBLS,
REMAINING LTR 4696 BBLS

ON SALES: 365 MCF, 0 BC, 600 BW, TP: 1500#, CP: 2950#, 20/64 CHK, 24HRS, LP: 262#.

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

AMENDED REPORT ☐ FORM 8
(highlight changes)

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. TYPE OF WELL: OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> DRY <input type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-23608
b. TYPE OF WORK: NEW WELL <input checked="" type="checkbox"/> HORIZ. LATS. <input type="checkbox"/> DEEP-EN <input type="checkbox"/> RE-ENTRY <input type="checkbox"/> DIFF. RESVR. <input type="checkbox"/> OTHER _____		6. IF INDIAN, ALLOTTEE OR TRIBE NAME
2. NAME OF OPERATOR: KERR MCGEE OIL & GAS ONSHORE LP		7. UNIT or CA AGREEMENT NAME UNIT #891008900A
3. ADDRESS OF OPERATOR: 1368 S 1200 E CITY VERNAL STATE UT ZIP 84078		8. WELL NAME and NUMBER: NBU 1021-13G
4. LOCATION OF WELL (FOOTAGES) AT SURFACE: 1444'FNL, 2651'FEL AT TOP PRODUCING INTERVAL REPORTED BELOW: AT TOTAL DEPTH:		9. API NUMBER: 4304737723
10. FIELD AND POOL, OR WILDCAT NATURAL BUTTES		11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNE 13 10S 21E
12. COUNTY UINTAH		13. STATE UTAH

14. DATE SPUDDED: 11/27/2007	15. DATE T.D. REACHED: 12/20/2007	16. DATE COMPLETED: 2/2/2008	ABANDONED <input type="checkbox"/> READY TO PRODUCE <input checked="" type="checkbox"/>	17. ELEVATIONS (DF, RKB, RT, GL): 5255'GL
18. TOTAL DEPTH: MD 9,131 TVD	19. PLUG BACK T.D.: MD 9,000 TVD	20. IF MULTIPLE COMPLETIONS, HOW MANY? *		21. DEPTH BRIDGE MD PLUG SET: TVD
22. TYPE ELECTRIC AND OTHER MECHANICAL LOGS RUN (Submit copy of each) <i>MUDLOG, CBL-CCL-GR, HOLE VOLUME CAL, AT/SHALLOW FOCUSED, TRIAL COMBO, COMP PHOTO DEN/DN</i>		23. WAS WELL CORED? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit analysis) WAS DST RUN? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit report) DIRECTIONAL SURVEY? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit copy)		

24. CASING AND LINER RECORD (Report all strings set in well)									
HOLE SIZE	SIZE/GRADE	WEIGHT (#/ft.)	TOP (MD)	BOTTOM (MD)	STAGE CEMENTER DEPTH	CEMENT TYPE & NO. OF SACKS	SLURRY VOLUME (BBL)	CEMENT TOP **	AMOUNT PULLED
20"	14" STL	36.7#		40		28			
12 1/4"	9 5/8 J-55	36#		2,220		800			
7 7/8"	4 1/2 I-80	11.6#		9,131		1535			

25. TUBING RECORD								
SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)
2 3/8"	7.667							

26. PRODUCING INTERVALS <i>W/SMUD Per UNIT #A</i>					27. PERFORATION RECORD				
FORMATION NAME	TOP (MD)	BOTTOM (MD)	TOP (TVD)	BOTTOM (TVD)	INTERVAL (Top/Bot - MD)	SIZE	NO. HOLES	PERFORATION STATUS	
(A) MESAVERDE	7,310	8,904			7,310 8,904	0.36	236	Open <input checked="" type="checkbox"/>	Squeezed <input type="checkbox"/>
(B)								Open <input type="checkbox"/>	Squeezed <input type="checkbox"/>
(C)								Open <input type="checkbox"/>	Squeezed <input type="checkbox"/>
(D)								Open <input type="checkbox"/>	Squeezed <input type="checkbox"/>

28. ACID, FRACTURE, TREATMENT, CEMENT SQUEEZE, ETC.	
DEPTH INTERVAL	AMOUNT AND TYPE OF MATERIAL
7310'-8904'	PMP 10,721 BBLS SLICK H2O & 385,760# 30/50 OTTOWA SD

29. ENCLOSED ATTACHMENTS: <input type="checkbox"/> ELECTRICAL/MECHANICAL LOGS <input type="checkbox"/> SUNDRY NOTICE FOR PLUGGING AND CEMENT VERIFICATION <input type="checkbox"/> GEOLOGIC REPORT <input type="checkbox"/> CORE ANALYSIS <input type="checkbox"/> DST REPORT <input type="checkbox"/> OTHER: RECEIVED		30. WELL STATUS: PROD
---	--	-------------------------------------

31. INITIAL PRODUCTION

INTERVAL A (As shown in item #26)

DATE FIRST PRODUCED: 2/2/2008		TEST DATE: 2/7/2008		HOURS TESTED: 24		TEST PRODUCTION RATES: →		OIL – BBL: 0		GAS – MCF: 1,907		WATER – BBL: 784		PROD. METHOD: FLOWING							
CHOKE SIZE: 15/64		TBG. PRESS. 1,168		CSG. PRESS. 1,873		API GRAVITY		BTU – GAS		GAS/OIL RATIO		24 HR PRODUCTION RATES: →		OIL – BBL: 0		GAS – MCF: 1,907		WATER – BBL: 784		INTERVAL STATUS: PROD	

INTERVAL B (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

INTERVAL C (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

INTERVAL D (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

32. DISPOSITION OF GAS (Sold, Used for Fuel, Vented, Etc.)

SOLD

33. SUMMARY OF POROUS ZONES (Include Aquifers):

Show all important zones of porosity and contents thereof. Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

34. FORMATION (Log) MARKERS:

Formation	Top (MD)	Bottom (MD)	Descriptions, Contents, etc.	Name	Top (Measured Depth)
WASATCH MESAVERDE	4,451 7,140	7,140			

35. ADDITIONAL REMARKS (Include plugging procedure)

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records.

NAME (PLEASE PRINT) SHEILA UPCHEGO

TITLE SENIOR LAND ADMIN SPECIALIST

SIGNATURE

DATE 2/25/2008

This report must be submitted within 30 days of

- completing or plugging a new well
- drilling horizontal laterals from an existing well bore
- recompleting to a different producing formation
- reentering a previously plugged and abandoned well
- significantly deepening an existing well bore below the previous bottom-hole depth
- drilling hydrocarbon exploratory holes, such as core samples and stratigraphic tests

* ITEM 20: Show the number of completions if production is measured separately from two or more formations.

** ITEM 24: Cement Top – Show how reported top(s) of cement were determined (circulated (CIR), calculated (CAL), cement bond log (CBL), temperature survey (TS)).

Send to: Utah Division of Oil, Gas and Mining
1594 West North Temple, Suite 1210
Box 145801
Salt Lake City, Utah 84114-5801

Phone: 801-538-5340

Fax: 801-359-3940

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-2608
2. NAME OF OPERATOR: KERR McGEE OIL & GAS ONSHORE LP		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 1368 SOUTH 1200 EAST CITY VERNAL STATE UT ZIP 84078		7. UNIT or CA AGREEMENT NAME: UNIT #891008900A
PHONE NUMBER: (435) 781-7024		8. WELL NAME and NUMBER: NBU 1021-13G
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1444'FNL, 2651'FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNE 13 10S 21E		9. API NUMBER: 4304737723
		10. FIELD AND POOL, OR WILDCAT: NATURAL BUTTES
		COUNTY: UINTAH
		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input checked="" type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	


12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

THE OPERATOR REQUESTS AUTHORIZATION TO RECOMPLETE THE SUBJECT WELL LOCATION. THE OPERATOR PROPOSES TO COMPLETE THE WASATCH FORMATION, AND COMMINGLE THE NEWLY WASATCH FORMATION WITH THE EXISTING MESAVERDE FORMATION.

PLEASE REFER TO THE ATTACHED RECOMPLETION PROCEDURE.

Add new perms 4529' to 7028'

RECEIVED
AUG 19 2008
DIV. OF OIL, GAS & MINING

NAME (PLEASE PRINT) SHEILA UPCHEGO	TITLE REGULATORY ANALYST
SIGNATURE 	DATE 8/14/2008

(This space for State use only)

APPROVED BY THE STATE
OF UTAH DIVISION OF
OIL, GAS, AND MINING

DATE: 8/26/08

BY: 

*Case 173-14

(See Instructions on Reverse Side)

COPY SENT TO OPERATOR

Date: 8.27.2008

Initials: KS

Name: NBU 1021-13G
Location: SWNE-Section 13-T10S-R21E
Uintah County, UT
Date: 7/11/08

ELEVATIONS: 5255 GL 5270 KB

TOTAL DEPTH: 9131 **PBTD:** 9086
SURFACE CASING: 9 5/8", 36# J-55 ST&C @ 2230'
PRODUCTION CASING: 4 1/2", 11.6#, I-80 LT&C @ 9131'
 Marker Joint 4447'-4462'

TUBULAR PROPERTIES:

	BURST (psi)	COLLAPSE (psi)	DRIFT DIA. (in.)	CAPACITIES	
				(bbl/ft)	(gal/ft)
2 3/8" 4.7# J-55 tbg	7,700	8,100	1.901"	0.00387	0.1624
4 1/2" 11.6# I-80 (See above)	7780	6350	3.875"	0.0155	0.6528
2 3/8" by 4 1/2" Annulus				0.0101	0.4227

TOPS:

1247' Green River
 1981' Mahogany
 4451' Wasatch
 7179' Mesaverde
 Estimated T.O.C. from CBL @3450'

GENERAL:

- A minimum of **24** tanks (cleaned lined 500 bbl) of recycled water will be required. Note: Use biocide in tanks and the water needs to be at least 45°F at pump time.
- All perforation depths are from Weatherfords Induction-Density-Neutron log dated 12/08/07
- 7 fracturing stages required for coverage.
- Procedure calls for 8 CBP's (**8000** psi).
- Calculate open perforations after each breakdown. If less than 60% of the perforations appear to be open, ball out with 15% HCl.
- Put scale inhibitor 3 gals/1000 gals (in pad and 1/2 the ramp) and 10 gals/1000 gals in all flushes except the final stage. Remember to pre-load the casing with scale inhibitor for the very first stage with 10 gpt.
- 30/50 mesh Ottawa sand, **Slickwater frac.**
- Maximum surface pressure **6200** psi.
- Flush volumes are the sum of slick water and acid used during displacement (include scale inhibitor as mentioned above). **DO NOT OVERDISPLACE.** Stage acid and scale inhibitor if necessary to cover the next perforated interval.
- Service companies need to provide surface/production annulus pop-offs to be set for 1500 psi for each frac.
- Pump **resin coated sand** last 5,000# of all frac stages

- Tubing Currently Landed @~7667'
- Originally completed on 1/28/08

Existing Perforations:

Zones	Perforations		SPF	Holes
	Top, ft	Bottom, ft		
MESAVERDE	8894	8904	4	40
MESAVERDE	8432	8434	2	4
MESAVERDE	8492	8494	4	8
MESAVERDE	8528	8530	4	8
MESAVERDE	8594	8599	4	20
MESAVERDE	8144	8148	4	16
MESAVERDE	8263	8269	4	24
MESAVERDE	7852	7864	3	36
MESAVERDE	7522	7523	4	4
MESAVERDE	7580	7582	4	8
MESAVERDE	7642	7644	4	8
MESAVERDE	7720	7725	4	20
MESAVERDE	7310	7320	4	40

PROCEDURE:

1. MIRU. Control well with recycled water and biocide as required. ND WH, NU BOP's and test.
2. TOOH with 2-3/8", 4.7#, J-55 tubing (currently landed at ~7667'). Visually inspect for scale and consider replacing if needed.
3. If tbg looks ok consider running a gauge ring to 7108' (50' below proposed CBP). Otherwise P/U a mill and C/O to 7108' (50' below proposed CBP).
4. Set 8000 psi CBP at ~ 7058'. Pressure test BOP and casing to 6000 psi. .
5. Perf the following with 3-3/8" gun, 23 gm, 0.36"hole:

Zone	From	To	spf	# of shots
WASATCH	6902	6906	4	16
WASATCH	6994	6997	4	12
WASATCH	7025	7028	4	12
# of Perfs/stage				40
6. Breakdown perfs and establish injection rate (include scale inhibitor in fluid). Fracture as outlined in Stage 1 on attached listing. Under-displace to ~6852' and trickle 250gal 15%HCL w/ scale inhibitor in flush. **Note: Stage has tight spacing.**
7. Set 8000 psi CBP at ~6837'. Perf the following 3-3/8" gun, 23 gm, 0.36"hole:

Zone	From	To	spf	# of shots
WASATCH	6713	6716	3	9

WASATCH	6769	6772	2	6
WASATCH	6800	6807	4	28
# of Perfs/stage				43

8. Breakdown perfs and establish injection rate. Fracture as outlined in Stage 2 on attached listing. Under-displace to ~6663' and trickle 250gal 15%HCL w/ scale inhibitor in flush.

9. Set 8000 psi CBP at ~6608'. Perf the following with 3-3/8" gun, 23 gm, 0.36" hole:

Zone	From	To	spf	# of shots
WASATCH	6418	6422	4	16
WASATCH	6572	6578	4	24
# of Perfs/stage				40

10. Breakdown perfs and establish injection rate. Fracture as outlined in Stage 3 on attached listing. Under-displace to ~6368' trickle 250gal 15%HCL w/ scale inhibitor in flush. **Note: Stage pumped at a reduced rate.**

11. Set 8000 psi CBP at ~6153'. Perf the following with 3-3/8" gun, 23 gm, 0.36" hole:

Zone	From	To	spf	# of shots
WASATCH	6002	6006	4	16
WASATCH	6117	6123	4	24
# of Perfs/stage				40

12. Breakdown perfs and establish injection rate. Fracture as outlined in Stage 4 on attached listing. Under-displace to ~5952' and trickle 250gal 15%HCL w/ scale inhibitor in flush.

13. Set 8000 psi CBP at ~5854'. Perf the following with 3-3/8" gun, 23 gm, 0.36" hole:

Zone	From	To	spf	# of shots
WASATCH	5710	5713	4	12
WASATCH	5790	5794	4	16
WASATCH	5821	5824	4	12
# of Perfs/stage				40

14. Breakdown perfs and establish injection rate. Fracture as outlined in Stage 5 on attached listing. Under-displace to ~5660' and trickle 250gal 15%HCL w/ scale inhibitor in flush.

15. Set 8000 psi CBP at ~5291'. Perf the following with 3-3/8" gun, 23 gm, 0.36" hole:

Zone	From	To	spf	# of shots
WASATCH	5206	5208	3	6
WASATCH	5242	5244	4	8
WASATCH	5251	5261	3	30
# of Perfs/stage				44

16. Breakdown perfs and establish injection rate. Fracture as outlined in Stage 6 on attached listing. Under-displace to ~5156' and trickle 250gal 15%HCL w/ scale inhibitor in flush. **Note: Stage pumped at a reduced rate**

17. Set 8000 psi CBP at ~4714'. Perf the following 3-3/8" gun, 23 gm, 0.36" hole:

Zone	From	To	spf	# of shots
WASATCH	4529	4531	4	8
WASATCH	4670	4674	4	16
WASATCH	4680	4684	4	16
# of Perfs/stage				40

18. Breakdown perfs and establish injection rate. Fracture as outlined in Stage 7 on attached listing. Under-displace to ~4479' and flush only with recycled water.
19. Set 8000 psi CBP at ~4479'.
20. TIH with 3 7/8" bit, pump off sub, SN and tubing.
21. Drill plugs and clean out to PBTD Pump off sub and land tubing at $\pm 8350'$ unless indicated otherwise by the well's behavior. This well will be commingled at this time.
22. RDMO

For design questions, please call
David Cocciolone, Denver, CO
(832)-453-2043 (Cell)
(720)-929-6716 (Office)

For field implementation questions, please call
Robert Miller, Vernal, UT
(435)-781-7041 (Office)

NOTES:

Well located In NBU Central, just to the West of Goat Pasture. Some stages are pumped at lower rates to avoid water.

NBU 1021-13G
Perforation and CBP Summary

Stage	Zones	Perforations		SPF	Holes	Fracture Coverage		
		Top, ft	Bottom, ft					
1	WASATCH		No Perfs			6835	to	6836
	WASATCH		No Perfs			6839	to	6840
	WASATCH		No Perfs			6850	to	6851
	WASATCH		No Perfs			6862	to	6864
	WASATCH		No Perfs			6866	to	6868
	WASATCH		No Perfs			6879	to	6881
	WASATCH		No Perfs			6882	to	6885
	WASATCH		No Perfs			6900	to	6900
	WASATCH	6902	6906	4	16	6903	to	6905
	WASATCH		No Perfs			6919	to	6920
	WASATCH		No Perfs			6952	to	6953
	WASATCH	6994	6997	4	12	6971	to	6972
	WASATCH		No Perfs			7013	to	7014
	WASATCH	7025	7028	4	12	7020	to	7022
	# of Perfs/stage				40	CBP DEPTH	6837	
2	WASATCH		No Perfs			6680	to	6681
	WASATCH		No Perfs			6701	to	6701
	WASATCH		No Perfs			6705	to	6706
	WASATCH	6713	6716	3	9	6711	to	6717
	WASATCH		No Perfs			6718	to	6718
	WASATCH		No Perfs			6748	to	6747
	WASATCH		No Perfs			6749	to	6750
	WASATCH		No Perfs			6754	to	6755
	WASATCH	6769	6772	2	6	6768	to	6772
	WASATCH		No Perfs			6786	to	6787
	WASATCH		No Perfs			6789	to	6792
	WASATCH		No Perfs			6796	to	6797
	WASATCH	6800	6807	4	28	6800	to	6804
	WASATCH		No Perfs			6810	to	6812
	# of Perfs/stage				43	CBP DEPTH	6608	
3	WASATCH		No Perfs			6330	to	6335
	WASATCH		No Perfs			6340	to	6346
	WASATCH		No Perfs			6376	to	6379
	WASATCH	6418	6422	4	16	6411	to	6423
	WASATCH	6572	6578	4	24	6572	to	6576
	WASATCH		No Perfs			6578	to	6578
	WASATCH		No Perfs			6597	to	6598
	# of Perfs/stage				40	CBP DEPTH	6153	
4	WASATCH		No Perfs			5919	to	5919
	WASATCH		No Perfs			6001	to	6002
	WASATCH	6002	6006	4	16	6002	to	6005
	WASATCH		No Perfs			6013	to	6013
	WASATCH	6117	6123	4	24	6117	to	6121
	# of Perfs/stage				40	CBP DEPTH	5854	
5	WASATCH		No Perfs			5624	to	5625
	WASATCH		No Perfs			5637	to	5638
	WASATCH		No Perfs			5709	to	5710
	WASATCH	5710	5713	4	12	5710	to	5714
	WASATCH		No Perfs			5714	to	5715
	WASATCH		No Perfs			5722	to	5723
	WASATCH		No Perfs			5762	to	5762
	WASATCH		No Perfs			5773	to	5775
	WASATCH		No Perfs			5783	to	5788
	WASATCH	5790	5794	4	16	5790	to	5795
	WASATCH		No Perfs			5810	to	5811
	WASATCH	5821	5824	4	12	5814	to	5826
	# of Perfs/stage				40	CBP DEPTH	5291	
6	WASATCH		No Perfs			5203	to	5206
	WASATCH	5206	5208	3	6	5207	to	5208
	WASATCH		No Perfs			5209	to	5210
	WASATCH		No Perfs			5221	to	5223
	WASATCH		No Perfs			5228	to	5229
	WASATCH		No Perfs			5232	to	5234
	WASATCH		No Perfs			5235	to	5236
	WASATCH	5242	5244	4	8	5238	to	5247
	WASATCH	5251	5261	3	30	5248	to	5263
	WASATCH		No Perfs			5263	to	5268
	# of Perfs/stage				44	CBP DEPTH	4714	
7	WASATCH		No Perfs			4475	to	4476
	WASATCH		No Perfs			4527	to	4527
	WASATCH	4529	4531	4	8	4528	to	4531
	WASATCH		No Perfs			4531	to	4532
	WASATCH		No Perfs			4613	to	4613
	WASATCH		No Perfs			4663	to	4665
	WASATCH	4670	4674	4	16	4668	to	4672
	WASATCH		No Perfs			4672	to	4673
	WASATCH		No Perfs			4674	to	4681
	WASATCH	4680	4684	4	16	4682	to	4683
	WASATCH		No Perfs			4684	to	4689
	WASATCH		No Perfs			4693	to	4695
	# of Perfs/stage				40	CBP DEPTH	4,479	
Totals					287			

Fracturing Schedules
NBU 1021-13G
Slickwater Frac

Stage	Zone	Feet of Pay	Perfs Top, ft. Bot, ft.	SPF	Holes	Rate BPM	Fluid Type	Initial ppg	Final ppg	Fluid	Volume BBLs	Cum Vol BBLs	Fluid % of frac	Sand % of frac	Sand lbs	Cum. Sand lbs	Footage from CBP to Flush	Scale Inhib., gal.
1	WASATCH	1	No Perfs			Varied	Pump-in test			Slickwater	0	0						
	WASATCH	1	No Perfs			0	ISIP and 5 min ISIP											44
	WASATCH	1	No Perfs			50	Slickwater Pad			Slickwater	145	145	15.0%	0.0%	0	0		18
	WASATCH	2	No Perfs			50	Slickwater Ramp	0.25	1.25	Slickwater	482	627	50.0%	39.7%	15,188	15,188		30
	WASATCH	2	No Perfs			50	Slickwater Ramp	1.25	2	Slickwater	338	964	35.0%	60.3%	23,034	38,222		0
	WASATCH	2	No Perfs			50	Flush (4-1/2")				106	1,071				38,222		44
	WASATCH	3	No Perfs				ISDP and 5 min ISDP											137
	WASATCH	3	6902 6906		4	16												
	WASATCH	1	No Perfs															
	WASATCH	1	No Perfs															
	WASATCH	1	6994 6997		4	12												
	WASATCH	1	No Perfs															
	WASATCH	3	7025 7029		4	12												
		18	# of Perfs/stage		40										2,260	2,123	15	LOOK
						22.8	<< Above pump time (min)								gal/ft	CBP depth		
2	WASATCH	1	No Perfs			Varied	Pump-in test			Slickwater	0	0						
	WASATCH	1	No Perfs			0	ISIP and 5 min ISIP											29
	WASATCH	1	No Perfs			50	Slickwater Pad			Slickwater	228	228	15.0%	0.0%	0	0		48
	WASATCH	6	6713 6716		3	9	Slickwater Ramp	0.25	1.25	Slickwater	759	987	50.0%	39.7%	23,906	23,906		0
	WASATCH	1	No Perfs			50	Slickwater Ramp	1.25	2	Slickwater	531	1,518	35.0%	60.3%	36,258	60,164		43
	WASATCH	1	No Perfs			50	Flush (4-1/2")				104	1,621				60,164		119
	WASATCH	1	No Perfs				ISDP and 5 min ISDP											
	WASATCH	4	6769 6772		2	6												
	WASATCH	1	No Perfs															
	WASATCH	4	No Perfs															
	WASATCH	1	No Perfs															
	WASATCH	4	6800 6807		4	26												
	WASATCH	2	No Perfs															
		26	# of Perfs/stage		43										2,500	2,369	55	
						33.8	<< Above pump time (min)								gal/ft	CBP depth		
3	WASATCH	6	No Perfs			Varied	Pump-in test			Slickwater	0	0						
	WASATCH	3	No Perfs			0	ISIP and 5 min ISIP											36
	WASATCH	12	6418 6422		4	16	Slickwater Pad			Slickwater	286	286	15.0%	0.0%	0	0		60
	WASATCH	5	6572 6578		4	24	Slickwater Ramp	0.25	1.25	Slickwater	952	1,238	50.0%	39.7%	30,000	30,000		0
	WASATCH	1	No Perfs			40	Slickwater Ramp	1.25	2	Slickwater	667	1,905	35.0%	60.3%	45,500	75,500		40
	WASATCH	1	No Perfs			40	Flush (4-1/2")				99	2,004				75,500		136
							ISDP and 5 min ISDP											
		32	# of Perfs/stage		40										2,500	2,369	215	
						52.2	<< Above pump time (min)								gal/ft	CBP depth		
4	WASATCH	1	No Perfs			Varied	Pump-in test			Slickwater	0	0						
	WASATCH	1	No Perfs			0	ISIP and 5 min ISIP											9
	WASATCH	3	6002 6006		4	16	Slickwater Pad			Slickwater	68	68	15.0%	0.0%	0	0		14
	WASATCH	1	No Perfs			50	Slickwater Ramp	0.25	1.25	Slickwater	228	296	50.0%	39.7%	7,172	7,172		0
	WASATCH	4	6117 6123		4	24	Slickwater Ramp	1.25	2	Slickwater	159	455	35.0%	60.3%	10,877	18,049		38
						50	Flush (4-1/2")				93	548				18,049		51
							ISDP and 5 min ISDP											
		9	# of Perfs/stage		40										2,260	2,123	98	
						11.4	<< Above pump time (min)								gal/ft	CBP depth		
5	WASATCH	1	No Perfs			Varied	Pump-in test			Slickwater	0	0						
	WASATCH	1	No Perfs			0	ISIP and 5 min ISIP											34
	WASATCH	4	5710 5713		4	12	Slickwater Pad			Slickwater	269	269	15.0%	0.0%	0	0		57
	WASATCH	1	No Perfs			50	Slickwater Ramp	0.25	1.25	Slickwater	897	1,167	50.0%	39.7%	28,268	28,268		0
	WASATCH	1	No Perfs			50	Slickwater Ramp	1.25	2	Slickwater	628	1,795	35.0%	60.3%	42,870	71,135		34
	WASATCH	2	No Perfs			50	Flush (4-1/2")				88	1,883				71,135		125
							ISDP and 5 min ISDP											
	WASATCH	6	No Perfs															
	WASATCH	5	5790 5794		4	16												
	WASATCH	1	No Perfs															
	WASATCH	13	5821 5824		4	12												
		34	# of Perfs/stage		40										2,250	2,123	369	
						39.3	<< Above pump time (min)								gal/ft	CBP depth		
6	WASATCH	4	No Perfs			Varied	Pump-in test			Slickwater	0	0						
	WASATCH	2	5206 5208		3	6	ISIP and 5 min ISIP											37
	WASATCH	1	No Perfs			40	Slickwater Pad			Slickwater	293	293	15.0%	0.0%	0	0		62
	WASATCH	2	No Perfs			40	Slickwater Ramp	0.25	1.25	Slickwater	976	1,269	50.0%	39.7%	30,750	30,750		0
	WASATCH	2	No Perfs			40	Slickwater Ramp	1.25	2	Slickwater	583	1,952	35.0%	60.3%	46,638	77,388		31
	WASATCH	1	No Perfs			40	Flush (4-1/2")				80	2,033				77,388		129
							ISDP and 5 min ISDP											
	WASATCH	10	5242 5244		4	8												
	WASATCH	15	5251 5261		3	30												
	WASATCH	5	No Perfs															
		41	# of Perfs/stage		44										2,000	1,888	442	
						53.0	<< Above pump time (min)								gal/ft	CBP depth		
7	WASATCH	2	No Perfs			Varied	Pump-in test			Slickwater	0	0						
	WASATCH	1	No Perfs			0	ISIP and 5 min ISIP											27
	WASATCH	3	4529 4531		4	8	Slickwater Pad			Slickwater	214	214	15.0%	0.0%	0	0		45
	WASATCH	1	No Perfs			50	Slickwater Ramp	0.25	1.25	Slickwater	714	929	50.0%	39.7%	22,500	22,500		0
	WASATCH	2	No Perfs			50	Slickwater Ramp	1.25	2	Slickwater	500	1,429	35.0%	60.3%	34,125	56,625		0
	WASATCH	4	4670 4674		4	16	Flush (4-1/2")				70	1,498				56,625		72
							ISDP and 5 min ISDP											
	WASATCH	1	No Perfs															
	WASATCH	8	No Perfs															
	WASATCH	2	4680 4684		4	16												
	WASATCH	6	No Perfs															
	WASATCH	2	No Perfs															
		30	# of Perfs/stage		40										2,000	1,888	0	LOOK
						31.2	<< Above pump time (min)								gal/ft	CBP depth		
Totals		189			287						gals bbls	10,656 bbls			Total Sand	397,083		780
						4.1						23.7	tanks			Total Scale Inhib.		

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

AMENDED REPORT ☒ FORM 8
(highlight changes)

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. TYPE OF WELL:		OIL WELL <input type="checkbox"/>	GAS WELL <input checked="" type="checkbox"/>	DRY <input type="checkbox"/>	OTHER <input type="checkbox"/>	7. UNIT or CA AGREEMENT NAME UNIT #891008900A	
b. TYPE OF WORK:		NEW WELL <input type="checkbox"/>	HORIZ. LATS. <input type="checkbox"/>	DEEP-EN <input type="checkbox"/>	RE-ENTRY <input type="checkbox"/>	DIFF. RESVR. <input checked="" type="checkbox"/>	OTHER RECOMPLETE
2. NAME OF OPERATOR: KERR McGEE OIL & GAS ONSHORE LP						8. WELL NAME and NUMBER: NBU 1021-13G	
3. ADDRESS OF OPERATOR: 1368 S 1200 E CITY VERNAL STATE UT ZIP 84078				PHONE NUMBER: (435) 781-7024		9. API NUMBER: 4304737723	
4. LOCATION OF WELL (FOOTAGES) AT SURFACE: 1444'FNL, 2651'FEL AT TOP PRODUCING INTERVAL REPORTED BELOW: AT TOTAL DEPTH:						10. FIELD AND POOL, OR WILDCAT NATURAL BUTTES	
						11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNE 13 10S 21E	
						12. COUNTY UINTAH	13. STATE UTAH

14. DATE SPUDDED: 11/27/2007	15. DATE T.D. REACHED: 12/20/2007	16. DATE COMPLETED: 9/28/2008	ABANDONED <input type="checkbox"/>	READY TO PRODUCE <input checked="" type="checkbox"/>	17. ELEVATIONS (DF, RKB, RT, GL): 5255'GL
18. TOTAL DEPTH: MD 9,131 TVD	19. PLUG BACK T.D.: MD 9,040 TVD	20. IF MULTIPLE COMPLETIONS, HOW MANY? *		21. DEPTH BRIDGE PLUG SET: MD TVD	
22. TYPE ELECTRIC AND OTHER MECHANICAL LOGS RUN (Submit copy of each) N/A				23. WAS WELL CORED? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit analysis) WAS DST RUN? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit report) DIRECTIONAL SURVEY? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit copy)	

24. CASING AND LINER RECORD (Report all strings set in well)

HOLE SIZE	SIZE/GRADE	WEIGHT (#/ft.)	TOP (MD)	BOTTOM (MD)	STAGE CEMENTER DEPTH	CEMENT TYPE & NO. OF SACKS	SLURRY VOLUME (BBL)	CEMENT TOP **	AMOUNT PULLED
20"	14" STL	36.7#		40		28			
12 1/4"	9 5/8 J-55	36#		2,220		800			
7 7/8"	4 1/2 I-80	11.6#		9,131		1535			

25. TUBING RECORD

SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)
2 3/8"	8,356							

26. PRODUCING INTERVALS

FORMATION NAME	TOP (MD)	BOTTOM (MD)	TOP (TVD)	BOTTOM (TVD)	INTERVAL (Top/Bot - MD)	SIZE	NO. HOLES	PERFORATION STATUS
(A) WASATCH	4,529	7,028			4,529 7,028	0.36	245	Open <input checked="" type="checkbox"/> Squeezed <input type="checkbox"/>
(B)								Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
(C)								Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
(D)								Open <input type="checkbox"/> Squeezed <input type="checkbox"/>

27. PERFORATION RECORD

28. ACID, FRACTURE, TREATMENT, CEMENT SQUEEZE, ETC.

DEPTH INTERVAL	AMOUNT AND TYPE OF MATERIAL
4529'-7028'	PMP 10,884 BBLS SLICK H2O & 391,526# 30/50 SD

29. ENCLOSED ATTACHMENTS:

- | | | | |
|---|--|-------------------------------------|---|
| <input type="checkbox"/> ELECTRICAL/MECHANICAL LOGS | <input type="checkbox"/> GEOLOGIC REPORT | <input type="checkbox"/> DST REPORT | <input type="checkbox"/> DIRECTIONAL SURVEY |
| <input type="checkbox"/> SUNDRY NOTICE FOR PLUGGING AND CEMENT VERIFICATION | <input type="checkbox"/> CORE ANALYSIS | <input type="checkbox"/> OTHER: | |

30. WELL STATUS:

PROD

RECEIVED

OCT 20 2008

DIV. OF OIL, GAS & MINING

31. INITIAL PRODUCTION

INTERVAL A (As shown in item #26)

DATE FIRST PRODUCED: 9/28/2008		TEST DATE: 9/29/2008		HOURS TESTED: 24		TEST PRODUCTION RATES: →		OIL – BBL: 0		GAS – MCF: 1,781		WATER – BBL: 440		PROD. METHOD: FLOWING	
CHOKE SIZE: 18/64	TBG. PRESS. 812	CSG. PRESS. 1,289	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →		OIL – BBL: 0		GAS – MCF: 1,781		WATER – BBL: 440		INTERVAL STATUS: PROD	

INTERVAL B (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

INTERVAL C (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

INTERVAL D (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

32. DISPOSITION OF GAS (Sold, Used for Fuel, Vented, Etc.)

SOLD

33. SUMMARY OF POROUS ZONES (Include Aquifers):

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

34. FORMATION (Log) MARKERS:

Formation	Top (MD)	Bottom (MD)	Descriptions, Contents, etc.	Name	Top (Measured Depth)
WASATCH MESAVERDE	4,451 7,140				


35. ADDITIONAL REMARKS (Include plugging procedure)

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records.

NAME (PLEASE PRINT) SHEILA UPCHEGO

TITLE REGULATORY ANALYST

SIGNATURE



DATE

10/13/2008

This report must be submitted within 30 days of

- completing or plugging a new well
- drilling horizontal laterals from an existing well bore
- recompleting to a different producing formation

- reentering a previously plugged and abandoned well
- significantly deepening an existing well bore below the previous bottom-hole depth
- drilling hydrocarbon exploratory holes, such as core samples and stratigraphic tests

* ITEM 20: Show the number of completions if production is measured separately from two or more formations.

** ITEM 24: Cement Top – Show how reported top(s) of cement were determined (circulated (CIR), calculated (CAL), cement bond log (CBL), temperature survey (TS)).

Send to: Utah Division of Oil, Gas and Mining
1594 West North Temple, Suite 1210
Box 145801
Salt Lake City, Utah 84114-5801

Phone: 801-538-5340

Fax: 801-359-3940